


Alaska • Arizona • California • Colorado • Hawaii • Idaho • Montana
Nebraska • Nevada • New Mexico • North Dakota • Oklahoma
Oregon • South Dakota • Texas • Utah • Washington • Wyoming

Guide for Uniform Laws and Regulations Governing Truck Size and Weight Among the WASHTO States

Adopted by the WASHTO Policy Committee
June 2004

Western Association of State Highway and Transportation Officials



WASHTO Committee on Highway Transport

Chairman: Rick Clasby
Vice Chairman: Regina Phipps
Sponsor: Dave Galt/Montana

State	Primary Delegate	Alternate
ALASKA	Dan Breeden	Sue Grundberg
ARIZONA	Ric Athey	
CALIFORNIA	Steve Sowers	
COLORADO	Teresa Lawser	Wayne Lupton
HAWAII	Charles Yonamine	
IDAHO	Regina Phipps	Alan Frew
MONTANA	Carolyn Knuckles	
NEBRASKA	Ron Kontos	
NEVADA	Jan Christopherson	Dick Yeoman
NEW MEXICO	Cary Langeherwig	Rick Cox
NORTH DAKOTA	Dave Levi	Leanna Emmer
OKLAHOMA	Norm Hill	
OREGON	Ed Scrivner	
SOUTH DAKOTA	Ed Rodgers	
TEXAS	Carol Davis	Christy Smith
UTAH	Rick Clasby	Richard Ollerton
WASHINGTON	Tim Erickson	Jim Wright
WYOMING	Russell Howe	Lori Sopko

CONTRIBUTORS

CANADA

ALBERTA	Alvin Moroz
BRITISH COLUMBIA	Doug Elliot
MANITOBA	Greg Catteeuw
SASKATCHEWAN	Bob Billington
YUKON	John Warkentin
NORTHWEST TERRITORIES	Harris Beaulieu

MEXICO

DIRECTOR GENERAL DE TRANSPORTE TERRESTRE

Ing. Jose Aguilar Alcerreca

DIRECTOR DE DESARROLLO DEL AUTO TRANSPORTE FEDERAL

Lic. Dario Arrieta Leyva

	Page
Foreword	1
Mission Statement	2
Goals	2
Chapter 1.00 Definitions	3
Chapter 2.00 Vehicles in Regular Operation	7
2.01 Scope	7
2.02 Width	7
2.03 Height	7
2.04 Length	7
2.05 Maximum Weights	7
Bridge Formula Chart	9
Chapter 3.00 Routinely Permitted Oversize and Overweight Vehicles	11
3.01 Scope	11
3.02 Maximum Weights	11
3.03 Maximum Dimensions	11
3.04 Time of Movement	11
3.05 Route Restrictions	11
3.06 Pilot/Escort Vehicles	11
3.07 Lighting, Flagging, and Signing	11
Chapter 4.00 Regional Permitting	13
4.01 Scope	13
4.02 Envelope Vehicles	13
4.03 Jurisdiction of Issuance	13
4.04 Jurisdiction Contacts	14
4.05 Routes: Regional Highway Network	14
4.06 Special Conditions	14
4.07 Application and Permit Form	14
4.08 Period of Permit Validity, Extensions, and Amendments	15
4.09 Permitting Process	15
4.10 Vehicle Weight Table	17
4.11 Sample Western Regional Permit	19

Chapter 5.00 Superloads	21
5.01 Scope	21
5.02 Superload Permit Application	21
5.03 State Defining Size and Weight Criteria for Superloads	21
5.04 Superload Alert Process	21
5.05 Superloads Defined by State	24
Chapter 6.00 Manufactured Housing	27
6.01 Scope	27
6.02 Manufactured Housing Recommended for Interstate Permit Agreements	27
6.03 Manufactured Housing With a Base in Excess of 14 Feet Wide	27
6.04 Two Vehicle Requirements	28
6.05 Time of Travel	28
6.06 Lights, Signs, and Pilot/Escorts	28
Chapter 7.00 Lighting, Flagging, Signing, and Time of Movement Requirements	29
7.01 Scope	29
7.02 Lights, Flags, and Signs	29
7.03 Conditions Requiring Escorts	31
7.04 Time of Movement	31
Chapter 8.00 Pilot/Escort Vehicle Requirements	35
8.01 Scope	35
8.02 Pilot/Escort Vehicle Operator Certification	35
8.03 Pilot/Escort Vehicle Operational Procedures	36
8.04 Pilot/Escort Vehicle and Equipment Requirements	39
Chapter 9.00 Longer Combination Vehicles	41
9.01 Scope	41
9.02 Rocky Mountain Doubles	41
9.03 Turnpike Doubles	41
9.04 Triple Trailers	41
9.05 Maximum Weights	41
9.06 Permits	41
9.07 LCV General Permit Provisions	41
9.08 LCV Equipment	42
9.09 LCV Operational Requirements	43
9.10 LCV Driver Requirements	43
Longer Combination Vehicles Figures	44
Rocky Mountain Doubles	
Turnpike Doubles	
Triple Trailers	

	Page
Chapter 10.00 Standards for Permit Programs	45
10.01 Scope	45
10.02 Single Trip Permits	45
10.03 Permit Forms	45
10.04 Route Identification	45
10.05 Methods of Securing Permits	45
10.06 Methods of Payment	45
10.07 Sample Oversize/Overweight Permit	46
 Chapter 11.00 Retractable or Variable Load Suspension Axles	 49
11.01 Scope	49
11.02 Controlss	49
11.03 Axles Rating	49
11.04 Tires	49
 Appendices	 51
 Appendix A Vehicles in Regular Operation: National Network	
(U.S. Measurement)	52
(Metric Measurement)	54
 Appendix B Vehicles in Regular Operation: Non-national Network	
(U.S. Measurement)	56
(Metric Measurement)	58
 Appendix C Nondivisible Load Permits: National Network and Other Designated Highways	
(U.S. Measurement)	60
(Metric Measurement)	62
 Appendix D Transporting Manufactured Housing: National Network and Other Designated Highways	
(U.S. Measurement)	64
(Metric Measurement)	66

Appendix E	Pilot/Escort Vehicles: National Network and Other Designated Highways	
	(U.S. Measurement)	68
	(Metric Measurement)	70
Appendix F	Longer Combination Vehicles	
	(U.S. Measurement)	72
	(Metric Measurement)	74
Appendix G	Additional Longer Combination Vehicles	
	(U.S. Measurement)	76
	(Metric Measurement)	78
Appendix H	Canadian Vehicle Weight Limits	80
Appendix I	Canadian Dimension Limits	82
Appendix J	Mexican Vehicle Weight Limits	84
Appendix K	Mexican Vehicle Dimension Limits	92
Appendix L	WASHTO Resolution 13-04	100

The Western Association of Highway Transportation Officials (WASHTO) recognizes that the productivity of our transportation systems is the key to a viable national economy. They further recognize that the commercial users of our roadway system need assistance to navigate through the various administrative practices established by each jurisdiction to preserve the infrastructure and provide safety to the motoring public. In 1987, WASHTO Chief Administrative Officers adopted a resolution committing resources through the Subcommittee on Highway Transport (a full Committee since 1995) to work toward uniformity in truck size and weight issues among the WASHTO states.

The WASHTO resolution set in motion a unique and talent-laden approach to the problem of uniformity. Each WASHTO member jurisdiction, and each federal agency involved in vehicle size and weight, assigned experienced representatives to the Committee. In addition, the Committee invited representatives from industry to act as technical advisors. Industry representation has included the Western Trucking Association Executive Council, the Western Highway Institute and the Special Carriers and Riggers Association. Also included in Committee work has been the invaluable input from Canadian provincial representatives. The result has been an extremely dynamic and solution oriented group committed to making vehicle size and weight regulation as uniform as possible.

This “Guide” is one of the major products of the Committee. It is the result of continuous work performed by a variety of Committee focus groups, studying issues and providing recommendations for more unified approaches to common problems. The Guide provides recommended minimum standards for use by states in revising their regulatory process. By using the Guide, it is the hope of the Committee that industry will be able to move more easily between jurisdictions without eroding the necessary balance between freight, infrastructure and safety.

The Committee understands that each jurisdiction may require some exceptions based on road configurations and local issues. As a result, each jurisdiction maintains the right to develop special exceptions to these recommendations. The minimum standards, however, are expected to apply to the Interstate and primary routes, and any other road a state may determine as appropriate.

The Committee views the Guide as a “living document” and is committed to keeping it current, and to continue to report new recommendations deemed appropriate to enhance uniformity. This is the sixth edition of the Guide, first published in 1990, to be approved by the WASHTO Policy Committee.

WASHTO Committee on Highway Transport

Mission Statement

The mission of the WASHTO Committee on Highway Transport in partnership with the motor carrier industry is to promote uniform laws, regulations, and practices among member jurisdictions and other jurisdictions for the efficient movement of goods and services while ensuring the safety of all highway users and preserving the highway infrastructure.

Goals

1. To promote uniformity among the WASHTO states and other jurisdictions regarding statutes, regulations, and ITS/CVO and their impacts on the transport industry and highway safety.
2. To serve as a forum to review AASHTO's proposed policies on highway transport issues from a WASHTO perspective.
3. To review and monitor research, proposals, and federal and state regulations related to highway transport as they impact WASHTO members and to promote appropriate truck size and weight research where needed to assist in the fulfillment of the mission of the committee.
4. To provide a forum to share industry best practices among the WASHTO states. To maximize ITS/CVO applications for the safe and efficient movement of goods and services.
5. To provide communication with the motor carrier industry, chief DOT executive offices, other WASHTO committees, and other organizations regarding the work and the recommendations of this committee.

Words and phrases defined. In this chapter, the following words and phrases have the meaning specified.

- 1.01 AASHTO Guide:** A publication entitled Guide for Maximum Dimensions and Weights of Motor Vehicles and for the Operation of Nondivisible Load Oversize and Overweight Vehicles, published by the American Association of State Highway and Transportation Officials.
- 1.02 Axle:** The common axis of rotation of one or more wheels whether power-driven or freely rotating, and whether in one or more segments, and regardless of the number of wheels carried thereon.
- 1.03 Bus:** A motor vehicle designated primarily for the transportation of persons rather than property and having a passenger-carrying capacity of more than 15 persons including the driver, other than a taxi cab constructed and designed for transporting persons for commercial purposes.
- 1.04 Combination Length:** The total length of a combination of vehicles, i.e., truck tractor-semitrailer-trailer combination, measured from front bumper of the motor vehicle to the rear extremity of the last trailer including the connecting tongue(s).
- 1.05 Combined Trailer Length:** The total length of a combination of trailers measured from the front of the first trailer to the rear extremity of the last trailer including the connecting tongue(s).
- 1.06 Gross Weight:** The weight of a vehicle and/or combination of vehicles plus the weight of any load thereon.
- 1.07 Height:** The total vertical dimension of a vehicle above the ground surface including any load.
- 1.08 Length:** The total longitudinal dimension of a single vehicle, a trailer, or a semitrailer. Length of a trailer or semitrailer is measured from the front of the cargo-carrying unit to its rear, exclusive of all overhang, safety or energy efficiency devices, including air conditioning units, air compressors, flexible fender extensions, splash and spray suppressant devices, bolsters, mechanical fastening devices, and hydraulic lift gates.
- 1.09 Longer Combination Vehicle:** A combination of truck tractor, semitrailer, and trailer(s) which exceeds legal length dimensions and operates on highways by permit for transporting reducible loads.
- 1.10 Manufactured Housing:** A structure constructed according to HUD/FHA mobile home construction and safety standards transportable in one or more sections, which is built on a permanent chassis.
- 1.11 Modular Buildings:** A facility designed and constructed (of which does not include a permanent chassis) and is built to state building specifications.
- 1.12 Maximum Off Track:** The maximum difference in the path created by the center of the steering axle and the center of the rear most axle of the vehicle or vehicle combination during the negotiation of a turn.
- 1.13 Motor Vehicle:** A vehicle which is self-propelled or propelled by electric power obtained from overhead trolley wires, but not operating upon rails.

- 1.14 National Network:** Those interstate and other federal-aid primary highways on which commercial vehicles of the dimensions authorized by the Surface Transportation Assistance Act of 1982 are allowed to operate.
- 1.15 Nondivisible Load:** A load which cannot be readily or reasonably dismantled and which is reduced to a minimum practical size and weight. Portions of a load can be detached and reloaded on the same hauling unit provided that the separate pieces are necessary to the operation of the machine or equipment which is being hauled, if the arrangement does not exceed permitable limits.
- Federal definition of nondivisible load to be used for vehicles operating on the interstate is as follows: any load or vehicle exceeding applicable length or weight limits which, if separated into smaller loads or vehicles would: compromise the intended use of the vehicle, destroy the value of the load or vehicle, require more than 8 work hours to dismantle using appropriate equipment.
- 1.16 Overhang:** Rear overhang, the distance from the center of the last axle to the end of the load, or portion of the vehicle whichever is longer.
- 1.17 Permit:** A written authorization to move or operate on a highway a vehicle or combination of vehicles with or without a load of size and/or weight exceeding the limits prescribed for vehicles in regular operation.
- 1.18 Pilot/Escort Vehicle:** A motor vehicle used for the express purpose as a warning vehicle for extra-legal vehicles.
- 1.19 Pounds Per Inch of Tire Width:** A measure of load restriction based on rated tire size. The pounds per inch of tire width are determined by dividing the weight carried by an axle group in pounds by the number of tires in the group and dividing that result by the manufacturers rated tire width as indicated on the sidewall of the tire.
- 1.20 Regional Permit:** Permits issued for movement of certain nonreducible overweight and/or oversize vehicles and/or loads on highways designated by the jurisdictions participating in the "Western Regional Agreement for the Issuance of Permits for Overweight and/or Oversize Vehicles and/or Loads Involved in Interstate Travel."
- 1.21 Regular Operation:** The movement over highways of motor vehicles with dimensions and weights specified by state codes.
- 1.22 Retractable Axle:** An axle which can be separately raised and lowered by the driver of the vehicle but which may not have its weight bearing capacity regulated.
- 1.23 Rocky Mountain Double:** A combination of vehicles including a truck tractor pulling a long semitrailer and a shorter trailer.
- 1.24 Semitrailer:** Every single vehicle without motive power designed for carrying property and so designed in conjunction and used with a motor vehicle that some part of its own weight and that of its own load rests or is carried by another vehicle and having one or more load-carrying axles.
- 1.25 Single Axle:** An assembly of two or more wheels whose centers are in one transverse vertical plane or may be included between two parallel transverse planes 40 inches apart extending across the full width of the vehicle.

- 1.26 Single Unit:** A motor vehicle with no attached vehicles, i.e., truck, bus, truck tractor.
- 1.27 Steering Axle:** The axle or axles on the front of a motor vehicle that are activated by the operator to directly accomplish guidance or steerage of the motor vehicle and/or combination of vehicles.
- 1.28 Superload:** A superload is any load that would require special approval by one or more state permit offices because of dimensions or weight. The guidelines contained in this manual reflect maximum size and weight limits for routine issuance of permits. Loads in excess of the stated guidelines would require additional coordination between industry representatives and state officials. Additionally, loads that do not exceed the superload guidelines may also require special approval by individual states. Refer to Chapter 5 for suggested procedures, the superload map, and special conditions.
- 1.29 Tandem Axle:** Any two axles whose centers are more than 40 inches but not more than 96 inches apart and are individually attached to or articulated from (or both) a common attachment to the vehicle including a connecting mechanism designed to equalize the load between axles.
- 1.30 Trailer:** Every single vehicle without motive power designed for carrying property wholly on its own structure, drawn by a motor vehicle which carries no part of the weight and load of the trailer on its own wheels and having two or more load carrying axles.
- 1.31 Tow Vehicle:** A motor vehicle used to transport manufactured housing.
- 1.32 Tridem Axle:** Any three consecutive axles whose extreme centers are not more than 144 inches apart and are individually attached to or articulated from (or both) a common attachment to the vehicle including a connecting mechanism designed to equalize the load between axles.
- 1.33 Triple Trailer Combination:** A combination of vehicles including a truck tractor pulling a semitrailer and two trailers.
- 1.34 Truck:** A single unit motor vehicle used primarily for the transportation of property.
- 1.35 Truck Tractor:** A motor vehicle used primarily for drawing other vehicles and not so constructed as to carry a load other than a part of the weight of the vehicle and load so drawn.
- 1.36 Trunnion Axle:** An axle configuration with two individual axles mounted in the same transverse plane, with four tires on each axle, connected at a pivot point which allows each individual axle to oscillate in a vertical plane to provide constant and equal weight distribution on each individual axle.
- 1.37 Trunnion Axle Group:** Two or more consecutive trunnion axles, which are individually attached to, and/or articulated from, the vehicle by a weight equalizing suspension system.
- 1.38 Turnpike Double:** A combination of vehicles including a truck tractor pulling a long semitrailer and an additional long trailer.
- 1.39 Variable Load Suspension (VLS) Axle:** An axle which can be separately raised and lowered by the driver of the vehicle. These axles are controlled by hydraulic or air suspension systems or by a combination of these methods.
- 1.40 Vehicle:** A device in, upon, or by which any person or property may be transported or drawn upon a highway, except devices moved by human power or used exclusively upon stationary rails or tracks.

- 1.41 Wide Base Tires:** Wide base single tires are tires whose nominal section width is over 14 inches.
- 1.42 Width:** The total outside transverse dimension of a vehicle including any load or load-holding devices thereon, but excluding approved safety devices and tire bulge due to load.

2.01 Scope: The provisions of this chapter governing width, height, length, and permissible loads should apply to vehicles serving in regular operation, as defined in Chapter 1.00. Vehicles operating under permit are covered in Chapters 3.00, 4.00, 5.00, and 6.00.

2.02 Width: Maximum vehicle width: 102 inches.

2.03 Height: Maximum vehicle height: 14 feet.

2.04 Length:

2.04.1 Single unit maximum length: 45 feet.

2.04.2 Truck-trailer combination maximum length: 75 feet.

2.04.3 Truck tractor-semitrailer combination maximum length: 65 feet when operated on highways not on the National Network.

2.04.4 Semitrailer maximum length: at least 53 feet on the National Network.

2.04.5 Combination length for a truck tractor-semitrailer-trailer combination: no maximum on National Network. Combined trailer length for a truck tractor-semitrailer-trailer combination: 61 feet. These provisions allow adequately for double 28-foot or double 28 $\frac{1}{2}$ -foot trailers.

2.05 Maximum Weights:

2.05.1 The maximum load per tire measured by pounds per inch of tire width shall be:

Steering Axle	600 lb/in
All other Axles	500 lb/in

Except for the steering axles or wide base single tires described below, all axles weighing more than 10,000 pounds shall have at least four tires per axle.

In lieu of four tires per axle, an axle may be equipped with wide base tires, limited to 500 pounds per inch of tire width.

Every state reserves the right to permit or otherwise establish limits in excess of those described above for use on vehicle configurations designed to address specific safety or economic concerns.

Each state shall determine effective dates based upon local economic, safety, and technological considerations. Amortization of investment and phasing out of single tires to minimize economic and operating disruption of individual companies and effected industries shall be considered factors.

2.05.2 Axle and Gross Weights: The maximum single axle weight shall be 20,000 pounds. The maximum tandem axle weight shall be 34,000 pounds. The maximum gross weight of a vehicle or combination of vehicles computed in accordance with 2.05.3, shall be 80,000 pounds.

2.05.3 Axle Group Weights: The total gross weight in pounds imposed on the highway by any group of two or more consecutive axles on a vehicle or combination of vehicles, shall not exceed the values computed by Federal Bridge Formula "B" as follows:

$$W = 500 ((LN/N-1)+12N+36)$$

Where: W = Maximum weight in pounds carried on any group of two or more axles computed to the nearest 500 pounds.

L = Distance in feet between the extremities of any group of two or more consecutive axles.

N = Number of axles in the group under consideration.

Exceptions to the axle group weights specified above which are federally mandated should be provided for by individual state code.

Bridge Formula Chart

Distance in Feet Between First and Last Axle of Any Group of Consecutive Axles

	2 Axles	3 Axles	4 Axles	5 Axles	6 Axles	7 Axles	8 Axles	9 Axles
4	34,000							
5	34,000							
6	34,000							
7	34,000							
8	34,000							
8+	38,000	42,000						
9	39,000	42,500						
10	40,000	43,500						
11		44,000						
12		45,000	50,000					
13		45,500	50,500					
14		46,500	51,500					
15		47,000	52,000					
16		48,000	52,500	58,000				
17		48,500	53,500	58,500				
18		49,500	54,000	59,000				
19		50,000	54,500	60,000				
20		51,000	55,500	60,500	66,000			
21		51,500	56,000	61,000	66,500			
22		52,500	56,500	61,500	67,000			
23		53,000	57,500	62,500	68,000			
24		54,000	58,000	63,000	68,500	74,000		
25		54,500	58,500	63,500	69,000	74,500		
26		55,500	59,500	64,000	69,500	75,000		
27		56,000	60,000	65,000	70,000	75,500		
28		57,000	60,500	65,500	71,000	76,500	82,000	
29		57,500	61,500	66,000	71,500	77,000	82,500	
30		58,500	62,000	66,500	72,000	77,500	83,000	
31		59,000	62,500	67,500	72,500	78,000	83,500	
32		60,000	63,500	68,000	73,000	78,500	84,500	90,000
33			64,000	68,500	74,000	79,000	85,500	90,500
34			64,500	69,000	74,500	80,000	85,500	91,000
35			65,500	70,000	75,000	80,500	86,000	91,500
36			68,000	70,500	75,500	81,000	86,500	92,000
37			68,000	71,000	76,000	81,500	87,000	93,000
38			68,000	71,500	77,000	82,000	87,500	93,500
39			68,000	72,500	77,500	82,500	88,500	94,000
40			68,500	73,000	78,000	83,500	89,000	94,500
41			69,500	73,500	78,500	84,000	89,500	95,000
42			70,000	74,000	79,000	84,500	90,000	95,500
43			70,500	75,000	80,000	85,000	90,500	96,000
44			71,500	75,500	80,500	85,500	91,000	96,500
45			72,000	76,000	81,000	86,000	91,500	97,500
46			72,500	76,500	81,500	87,000	92,500	98,000
47			73,500	77,500	82,000	87,500	93,000	98,500
48			74,000	78,000	83,000	88,000	93,500	99,000
49			74,500	78,500	83,500	88,500	94,000	99,500

	2 Axles	3 Axles	4 Axles	5 Axles	6 Axles	7 Axles	8 Axles	9 Axles
50			75,500	79,000	84,000	89,000	94,500	100,000
51			76,000	80,000	84,500	89,500	95,000	100,500
52			76,500	80,500	85,000	90,500	95,500	101,000
53			77,500	81,000	86,000	91,000	96,500	102,000
54			78,000	81,500	86,500	91,500	97,000	102,500
55			78,500	82,500	87,000	92,000	97,500	103,000
56			79,500	83,000	87,500	92,500	98,000	103,500
57			80,000	83,500	88,000	93,000	98,500	104,000
58				84,000	89,000	94,000	99,000	104,500
59				85,000	89,500	94,500	99,500	105,000
60				85,500	90,000	95,000	100,500	105,500
61				86,000	90,500	95,500	101,000	105,500
62				87,000	91,000	96,000	101,500	105,500
63				87,500	92,000	96,500	102,000	105,500
64				88,000	92,500	97,500	102,500	105,500
65				88,500	93,000	98,000	103,000	105,500
66				89,500	93,500	98,500	103,500	105,500
67				90,000	94,000	99,000	104,500	105,500
68				90,500	95,000	99,500	105,000	105,500
69				91,000	95,500	100,00	105,500	105,500
70				92,000	96,000	101,00	105,500	105,500
71				92,500	96,500	101,50	105,500	105,500
72				93,000	97,000	102,00	105,500	105,500
73				93,500	98,000	102,50	105,500	105,500
74				94,500	98,500	103,00	105,500	105,500
75				95,000	99,000	103,50	105,500	105,500
76				95,500	99,500	104,50	105,500	105,500
77				96,000	100,00	105,00	105,500	105,500
78				97,000	101,00	105,50	105,500	105,500
79				97,500	101,50	105,50	101,500	105,500
80				98,000	102,00	105,50	105,500	105,500
81				98,500	102,50	105,50	105,500	105,500
82				99,000	103,00	105,50	105,500	105,500
83				100,000	104,00	105,50	105,500	105,500
84					104,50	105,50	105,500	105,500
85					105,00	105,50	105,500	105,500
86+					105,50	105,50	105,500	105,500

Some states maximum gross weight limits may be less than or greater than 105,500 pounds. See appendix in the back of the book for each states maximum gross weight limits with and without permits.

Routinely Permitted Chapter 3.00 Oversize and Overweight Vehicles

- 3.01 Scope:** These guides pertain to routinely permitted nondivisible load vehicles moving over the National Network and other state highways designated by the individual states. It is intended that the guidelines provided herein will establish a basis for WASHTO interstate permit agreements.
- 3.02 Maximum Weights:**
- 3.02.1 Pounds Per Inch of Tire Width:** The maximum load on any tire on a vehicle or vehicle combination shall be 600 lb/in.
- 3.02.2 Single Axle:** The maximum load on a single axle equipped with dual tires (four tires/axle) shall be 24,000 pounds.
- 3.02.3 Tandem Axles:** The maximum load on a tandem axle (four tires/axle) shall be 45,000 pounds.
- 3.02.4 Tridem and Trunnion Axles:** When used in interstate truck transportation, the maximum load on either tridem or trunnion axle shall not exceed 60,000 pounds for routine permitting. Maximum loads above 60,000 pounds would be subject to each states permitting requirements or analysis.
- 3.02.5 Manufacturer's Ratings:** Where the manufacturer's ratings for tires, axles, or axle groups is less than the maximum weights recommended in this section, the manufacturer's rating will govern.
- 3.03 Maximum Dimensions:**
- 3.03.1 Width:** Maximum width of the vehicle or combination of vehicles, including load, shall not exceed 10 feet.
- 3.03.2 Height:** Maximum height of the vehicle or combination of vehicles, including load, shall not exceed 14 feet.
- 3.03.3 Length:** Maximum length of the vehicle or combination of vehicles, including load, shall not exceed 90 feet.
- 3.04 Time of Movement:** Oversize/overweight vehicles, which meet the requirements of this chapter, shall not be subject to time-of-day, weekend, or holiday movement restrictions, except for special circumstances dictated by each state.
- 3.05 Route Restrictions:** Oversize vehicles, which meet the requirements of this chapter, shall be restricted to highways with four or more traffic lanes and shall be further restricted to use of service facilities and commercial areas immediately adjacent to those highways.
- 3.06 Pilot/Escort Vehicles:** Oversize/overweight vehicles, which meet the requirements of this chapter, shall not require pilot/escorts except for special circumstances dictated by each state.
- 3.07 Lighting, Flagging, and Signing:** Oversize vehicles shall be equipped with flags, signs, and lights in accordance with Chapter 5.00.

4.01 Scope: The purpose of this chapter is to describe the basic common procedures used to issue permits for movement of certain non-divisible oversize and/or overweight vehicles on highways designated by the jurisdictions participating in the “Western Regional Agreement.”

4.02 Envelope Vehicle: Each member jurisdiction may issue regional permits allowing operations in any other member jurisdiction of the following non-reducible maximum dimensions:

4.02.1 Weight

1. 600 pounds per inch of tire width.
2. 21,500 pounds per axle.
3. 43,000 pounds per tandem axle.
4. 53,000 pounds per tridem (wheelbase more than 8 feet and less than 13 feet).
5. 160,000 pounds gross weight.
6. In no case may the gross weight exceed the sum of the permitted axle, group axle weights or the weight specified by the permit, whichever is less.
7. A minimum of five axles are required when hauling (i.e., tractor/semi-trailer combination). Self-propelled or towed vehicles may have less than five axles.
8. The weight on any group of axles shall be determined by the weight table on page 17. Other provisions of this section shall also apply, the lesser of these weights shall be the determining factor.

4.02.2 Length: 110 feet overall. The Agreement does not authorize permits for a semi-trailer longer than 53 feet to carry more than one item, or for any unladen semi-trailer longer than 53 feet used in a truck-tractor and semi-trailer combination.

Movement of unladen vehicles must comply with the limitations of the jurisdiction being traveled through (i.e. loading jeep and/or booster onto trailer when semi-trailer exceeds 62 feet in Oregon).

Note: To avoid unnecessary enforcement action in certain jurisdictions, both **overall length** and **trailer length** must be included on the permit.

4.02.3 Width: 14 feet

4.02.4 Height: 14 feet

4.03 Jurisdiction of Issuance: For vehicles falling within the size and weight limitations as described in the envelope vehicle definition, Member Jurisdictions may issue permits and collect fees for all Member Jurisdictions when they are either the entry/origin, destination/exit, or a pass through jurisdiction on the route. This restriction is designed to allocate the burden of permit writing among the member jurisdictions.

Regardless of which Member Jurisdiction writes the permit, the permit must be acquired prior to any significant movement within any of the Member jurisdictions.

4.04 Jurisdiction Contacts: A list of the contact person for each member jurisdiction is included in the Agreement.

4.05 Routes: Regional Highway Network: The Member Jurisdictions jointly develop and maintain a regional highway network map. Each regional permit may only authorize a permittee to travel on routes designated as part of the regional highway network, with the following exceptions:

1. The issuing jurisdiction may issue a regional permit authorizing travel off of the regional highway network within the borders of the issuing jurisdiction.
2. The issuing jurisdiction may issue a regional permit authorizing travel off the regional highway network when authorization is obtained from the affected jurisdiction.

4.05.1 Current Map Maintained by a Designated Jurisdiction: A single state shall be designated to maintain the current regional highway network map. Map revisions are to be provided to that state representative.

4.05.2 Regional Highway Network Modifications: Each Member Jurisdiction is responsible to notify the designated state of all restrictions on the network, such as detours due to construction or spring load limits. Notification of changes shall be made at least (7) days prior to the effective date of the proposed change, unless an emergency occurs which would not allow advance notice. The designated state will maintain the list of restrictions for each state and distribute copies to each member. Updates are sent out within three days of when the designated state is notified of a change.

In the event of an emergency change in the network, the Member Jurisdictions should make reasonable efforts to notify all other Member Jurisdictions by telephone or FAX of the change and immediately follow up with written notification.

4.05.3 Routes Covered: The Agreement applies only to the highways of the Regional Network. When a permittee must use highways off the Regional Network (i.e. local jurisdiction), the permittee must contact the non-member jurisdiction to obtain any necessary permit. Member jurisdictions must make a notation on any regional permits issued when the permittee must contact a non-member jurisdiction for route approval.

4.06 Special Conditions: Each jurisdiction involved in the Agreement has developed special conditions for travel. The conditions are attached to the permit and include such restrictions as special signing, lighting, escort requirements, or restrictions on days or times of travel.

4.06.1 All Current Special Conditions Maintained by Designated Jurisdiction: A single state shall be designated to maintain the list of special conditions for each state and distribute copies to each member. Updates are sent out within three days of when the designated state is notified of a change.

4.06.2 Modifications: Any changes to a member's special conditions must be conveyed to the designated state 14 days prior to the effective date. In the event of an emergency change in conditions the member making the change should notify the other members by FAX and follow up with written notification.

4.07 Application and Permit Form: A sample permit form is included on pages 19 and 20. This single trip permit will be valid for a period of five working days, for use by the permitted vehicle only (tractor and trailer).

4.08 Period of Permit Validity, Extensions, and Amendments:

- 4.08.1** Permits may be issued not more than five (5) calendar days in advance of the effective date to assist permittee scheduling and permit offices in leveling work load. Additional advance issuance could jeopardize safety due to the changing status of the system, such as detours, maintenance activities, etc.
- 4.08.2** One extension of up to five days may be granted upon a showing by the permittee that weather or road conditions or a mechanical failure of the vehicle precluded completion of the permitted trip during the initial five-day period.
- 4.08.3** An amendment may be allowed for vehicle information, weight and/ or dimension due to a mechanical failure and resulting equipment transfer while in route. Routes may also be amended due to an emergent restriction put in place while in route.
- 4.08.4** An extension or amendment should be made by the issuing jurisdiction, unless either of these only affect your jurisdiction. A hard copy of the extension and/or amendments must accompany the original permit for review by other affected jurisdictions. Hand written corrections on the original permit are not acceptable unless they affect only your jurisdiction.

A jurisdiction may charge for amendments to permits.

4.09 Permitting Process:

- 4.09.1** Overview: When all of the procedures required to implement this program are in place, the following briefly describes how the process should work:
 1. The truck industry, permit service companies and all interested parties will be given copies of the regional highway network map and a summary of the requirements for operating envelope vehicles under the Regional Agreement (as contained in this document). Each truck driver using these procedures is strongly encouraged to carry a copy of this map on board the permitted vehicle.
 2. Each jurisdiction will be responsible for publicizing the regional permitting program and related procedures.
 3. The truck operator requiring a regional permit for a non-divisible overweight or oversize vehicle that falls within the limits of the Agreement will contact the issuing jurisdiction and request a permit for a specific trip (with a specific origin and destination) and for a specific vehicle.
 4. If the vehicle and the highway route required to make the trip falls entirely within the limits of the Agreement, the issuing jurisdiction will:
 - a. Issue the regional permit.
 - b. Collect the fees, that are the sum of all the individual fees of each jurisdiction through which the envelop vehicle will travel.
 - c. Designate the specific routes that can be used.

5. If the issuing jurisdiction is issuing a permit that terminates in another member jurisdiction, and the permittee is going to leave the designated system, **the issuing jurisdiction must contact the member jurisdiction** in which the movement is exiting the regional network. They must give permission to exit the network before the permit is to be issued. The name of the contact person should be included on the permit
6. If one (or more) of the requirements of this common procedure are not met for one or more jurisdictions, then the issuing jurisdiction will require the truck operator to obtain individual state permits in those states where the requirements cannot be met.
7. After receiving the regional permit, the truck operator must also comply with all the special conditions attached to the permit.
8. Each jurisdiction will be responsible for the enforcement of the non-divisible oversize and overweight laws within its own boundaries. The regional permit will be valid in each jurisdiction for which it has been issued. However, if the requirements of the permit have been violated in a particular jurisdiction, the individual requirements of that jurisdiction will be enforced. Any fines collected within that jurisdiction will continue to be retained in that jurisdiction with no reimbursement being made to any other jurisdiction (including the issuing jurisdiction).

4.09.2 Transmittal of Fees:

1. A log and/or copies of regional permits must be maintained. A summary report, itemizing permits affecting a specific jurisdiction, or copies of the permits, are to accompany the transmittal to each jurisdiction as support for the fees being remitted.
2. The summary report, if used, must contain a list of permit numbers, the name of the carriers, issue date, fee, and type of permit (i.e., oversize, overweight, size and weight, or overlength). This information is used by the state for federal reporting and other statistical purposes.
3. Transmittals are to be prepared monthly with the actual remittance occurring as timely as possible after the completion of each calendar month.

4.09.3 Fee Calculation: Each jurisdiction has developed its own current fee schedule and method for collecting the fees. The most current fees will be maintained in a desk guide for use by each member jurisdiction.

Note: No permit fees will be charged when issuing a Regional Permit to marked vehicles belonging to, and operated by, government entities (i.e. marked military vehicles).

4.10 Vehicle Weight Table:

Maximum load in pounds carried on any group of 2 or more consecutive axles
Distance in Feet Between First and Last Axle of Any Group of Consecutive Axles

	2 Axles	3 Axles	4 Axles	5 Axles	6 Axles	7 Axles	8 Axles	9 Axles	10 Axles
4	43000								
5	43000								
6	43000								
7	43000								
8	43000	53000							
9	43000	53000							
10	43000	53000							
11		53000							
12		53000	70000						
13		53000	70900						
14		64500	71900						
15			72800						
16			73700	81200					
17			74700	82100					
18			75600	83000					
19			76500	83300					
20			77500	87400					
21			78400	85600					
22			79300	86500					
23			80300	87300					
24			81200	88200					
25			82100	89100					
26			83100	90000					
27			84000	90800					
28			84900	97200	99100				
29			85900	92600	100000				
31				94300	101600				
32				95200	102500				
33				96100	103300				
34				97000	104200				
35				97800	105000				
36				98700	105800				
37				99600	106700				
38				100500	107500				
39				101300	108400				
40				102200	109200				
41				103100	110000				
42				104000	110900				
43				104800	111700				
44				105700	112600				
45				106600	113400				
46				107500	114200	121600			
47					115100	122400			
48					115900	123200			
49					116800	124000			

	2 Axles	3 Axles	4 Axles	5 Axles	6 Axles	7 Axles	8 Axles	9 Axles	10 Axles
50					117600	124800			
51					118400	125700			
52					119300	126500			
53					120100	127300			
54					121000	128100	135600	143300	151200
55					121800	128900	136400	144100	152000
56					122600	129700	137200	144900	152800
57					123500	130600	138000	145700	153500
58					124300	131400	138800	146500	154300
59					125200	132200	139600	147300	155100
61					126800	133800	141200	148800	156600
62					127700	134600	142000	149600	157400
63					128500	135500	142800	150400	158200
64					129000	136300	143600	151200	159000
65						137100	144400	152000	159800
66						137900	145200	152800	160000
67						138700	146000	153600	
68						139500	146800	154400	
69						140400	147600	155100	
70						141200	148400	155900	
71						142000	149200	156700	
72						142800	150000	157500	
73						143600	150800	158300	
74						144400	151600	159100	
75						145300	152400	159900	
76						146100	153200	160000	
77						146900	154000		
78						147700	154800		
79						148500	155600		
80						149300	156400		
81						150200	157200		
82						150500	158000		
83							158800		
84							159600		
85							160000		

Note: In Oklahoma a 9 or 10 axle configuration is limited to the allowances under the 8 axle configuration column.

4.11 Sample Western Regional Permit:

<u>WESTERN REGIONAL PERMIT</u>						<div style="border: 1px solid black; padding: 10px; width: 150px; margin: 0 auto;"> State Logo </div>																																														
Permit Number:		Start:		Expires:																																																
Location:		Agent Name:																																																		
Company Name:																																																				
Address:																																																				
Vehicle/Axle:	Truck -	Trailer-	Tractor -	Semi-Trailer -	Self Prop. -	Other -																																														
License:	VIN:		Unit:		Base State:																																															
Transporting(Item):																																																				
Origin:				Destination:																																																
Routing:																																																				
Restriction:																																																				
<table style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="text-align: left;"><u>Weight</u></th> <th style="text-align: center;"><u>(LB)</u></th> <th style="text-align: center;"><u>(KG)</u></th> <th style="text-align: left;"><u>Dimensions</u></th> <th style="text-align: center;"><u>(FT - In)</u></th> <th style="text-align: center;"><u>(Meters)</u></th> <th style="text-align: left;"><u>Dimensions</u></th> <th style="text-align: center;"><u>(FT - In)</u></th> <th style="text-align: center;"><u>(Meters)</u></th> </tr> </thead> <tbody> <tr> <td>Gross Vehicle WT</td> <td></td> <td></td> <td>Max Height</td> <td></td> <td></td> <td>Front overhang</td> <td></td> <td></td> </tr> <tr> <td>Gross Axle WT</td> <td></td> <td></td> <td>Max Width</td> <td></td> <td></td> <td>Rear overhang</td> <td></td> <td></td> </tr> <tr> <td>Legal Axle WT</td> <td></td> <td></td> <td>Total Length</td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>Excess Axle WT</td> <td></td> <td></td> <td>Trailer Length</td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </tbody> </table>								<u>Weight</u>	<u>(LB)</u>	<u>(KG)</u>	<u>Dimensions</u>	<u>(FT - In)</u>	<u>(Meters)</u>	<u>Dimensions</u>	<u>(FT - In)</u>	<u>(Meters)</u>	Gross Vehicle WT			Max Height			Front overhang			Gross Axle WT			Max Width			Rear overhang			Legal Axle WT			Total Length						Excess Axle WT			Trailer Length					
<u>Weight</u>	<u>(LB)</u>	<u>(KG)</u>	<u>Dimensions</u>	<u>(FT - In)</u>	<u>(Meters)</u>	<u>Dimensions</u>	<u>(FT - In)</u>	<u>(Meters)</u>																																												
Gross Vehicle WT			Max Height			Front overhang																																														
Gross Axle WT			Max Width			Rear overhang																																														
Legal Axle WT			Total Length																																																	
Excess Axle WT			Trailer Length																																																	
<table style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="text-align: left;"><u>ST</u></th> <th style="text-align: left;"><u>Mile</u></th> <th style="text-align: left;"><u>Fee</u></th> <th style="text-align: left;"><u>Legal(lb)</u></th> <th style="text-align: left;"><u>Excess(lb)</u></th> <th style="text-align: left;"><u>Legal(Kg)</u></th> <th style="text-align: left;"><u>Excess(Kg)</u></th> </tr> </thead> <tbody> <tr><td colspan="7" style="height: 100px;"></td></tr> </tbody> </table>								<u>ST</u>	<u>Mile</u>	<u>Fee</u>	<u>Legal(lb)</u>	<u>Excess(lb)</u>	<u>Legal(Kg)</u>	<u>Excess(Kg)</u>																																						
<u>ST</u>	<u>Mile</u>	<u>Fee</u>	<u>Legal(lb)</u>	<u>Excess(lb)</u>	<u>Legal(Kg)</u>	<u>Excess(Kg)</u>																																														
(SPECIAL CONDITIONS) Not Valid without Applicable State Conditions Attached - Sign in colored ink (not black) to validate permit. Carry fax permit in vehicle all times. READ THIS BEFORE SIGNING: Valid on State Highways ONLY. Other routes subject to local road authority. Weight and speed restrictions subject to spring breakup. Permittee is responsible for vertical clearances. Applicant's acceptance of permit certifies vehicle-load has been reduced to minimum practical size - weight and is an agreement to comply with all applicable State permit regulations and all applicable State or Federal Motor vehicle laws. By signing, the permittee				Total Fee:																																																
SIGNED X _____																																																				
PERMIT NOT VALID UNLESS SIGNED BY PERMITEE AGENT THEREOF																																																				

WESTERN REGIONAL PERMIT

Permit Number:			Starts :		Expires:	
Attachment						
Axle Spacing Information						
Axle Group #	Axles	Group Wgt(lb)	Tires	Axle Space		Tire Size
				Ft	In	

5.01 Scope: Superloads by definition are moves that require special approval. The chapter identifies recommended procedures for the approval process for superloads, specific size and weight criteria for each state's superload determination, and a sample form that may be used to notify other states of proposed moves.

5.02 Superload Permit Application:

5.02.1 The following information, at a minimum, should accompany the standard permit application:

1. Documentation that the move is in the public interest and that an alternative method of transport is not feasible.
2. A schematic or photograph of the item to be moved, including an explanation of why it cannot be moved in smaller pieces.
3. A schematic of the loaded vehicle(s), including axle loadings, axle spacings (measured from the center of each axle), tire sizes, number of tires per axle, and the proposed height, length and width of the configuration.
4. A traffic control plan depicting the route and specific procedures to be followed to provide safe movement along the route, including:
 - a. Identified locations where anticipated traffic delays will occur; and
 - b. Description of any lane restrictions; and
 - c. How pilot/escort vehicles and flag persons will be used; and
 - d. Arrangements for the movement of overhead obstacles; and
 - e. Identification of railroad crossings and contact information, including a pre-trip analysis of each crossing to assure vehicle(s) will clear the grade; and
 - f. Provisions for emergency vehicles to navigate around the configuration.

5.02.2 Each state should determine the most efficient means of analyzing superload requests and processing superload permits without jeopardizing safety or infrastructure preservation. Analysis and processing time for superloads should be set in policy and shared with industry.

5.03 State Definition of Size and Weight Criteria for Superloads: See map and notes on pages 24 and 25.

5.04 Superload Alert Process:

5.04.1 Using the criteria in the WASHTO Guide on pages 24 and 25, the WASHTO state receiving an inquiry or request for a permit, which exceeds maximum routine permit dimensions, should use the following procedure to assure that the appropriate states are notified of a possible "superload" move.

1. If the movement is a "superload" in one or more states, complete the superload alert fax transmittal sheet.
2. Advise the carrier that dimensions and/or weights require special handling by one or more of the states. The carrier should be advised to contact each state. Provide a contact name, phone number, and fax number for each state.
3. Send the completed fax transmittal sheet to each state involved in the move.

5.04.2 WASHTO Border states may wish to add their neighboring state even if that state is not a WASHTO member.

5.04.3 The following is a list of phone numbers and fax numbers for the WASHTO States Permit Offices.

Permit Offices	Phone Number	Fax Number
Alaska, Anchorage	(907) 341-3200	(907) 341-3221
Arizona, Phoenix	(623) 932-2247	(623) 932-2441
California, Sacramento	(916) 654-4828	(916) 654-3498
Colorado, Denver	(303) 757-9539	(303) 757-9719
Hawaii	(808) 831-6712	(808) 831-6725
Idaho, Boise	(208) 334-8420	(208) 334-8419
Montana, Helena	(406) 444-6130	(406) 444-7670
Nevada, Carson City	(775) 888-7410	(775) 888-7103
New Mexico, Santa Fe	(505) 827-0376	(505) 827-0384
North Dakota, Bismarck	(701) 328-2621	(701) 328-1642
Oklahoma, Oklahoma City	(405) 425-2334	(405) 425-0943
Oregon, Salem	(503) 373-0000	(503) 378-2873
South Dakota, Pierre	(605) 698-3925	(605) 698-7665
Texas, Austin	(800) 299-1700	(512) 465-3549
Utah, Salt Lake City	(801) 965-4508	(801) 965-4936
Washington, Olympia	(360) 704-6390	(360) 704-6350
Wyoming, Cheyenne	(307) 777-4376	(307) 777-4399

5.04.4 Superload Information Transmittal Sheet:

To: Fax Number

AK (907) 341-3221

AZ (623) 932-2411

CA (916) 654-3498

C0 (303) 757-9719

ID (208) 334-8419

MT (406) 444-7670

NV (775) 888-7103

NM (505) 827-0384

ND (701) 328-1642

OK (405) 425-0943

OR (503) 378-2873

SD (605) 698-7665

TX (512) 465-3549

UT (801) 965-4936

WA (360) 704-6350

WY (307) 777-4399

From: _____ Date: ____ / ____ / ____

Company Name: _____

Contract: _____

Load: _____

Dimensions: Width: _____ Length: _____

No. Axles: _____


Axle Spacings: _____

Route: _____

Other Information: _____

5.05 Superloads Defined by State:

5.05.1 Map:



5.05.2 Additional State Notes:**California:**

Special handling for width over 15 feet.

Maximum weights allowed on “purple chart” may not be exceeded. Additional axles must be added or weight of the load reduced to conform to “purple chart loading.” No exceptions are made. Acceptable hauling equipment should be used.

Hawaii:

Special handling and review by engineering is required if the following is exceeded:

Tread width of 8 feet, over 42,000 on a single axle.

Tread width of 8 feet, over 56,000 on a tandem.

Tread width of 9 feet, over 45,000 on a single axle.

Tread width of 9 feet, over 60,000 on a tandem.

Tread width of 10 feet, over 48,000 on a single axle.

Tread width of 10 feet, over 64,000 on a tandem.

Washington:

Special handling for height. It is the responsibility of the permittee to carefully plan the route. Some structures on state highways do not have a 14-foot clearance; many have less than 14 feet 6 inches. All movements in excess of 14 feet 6 inches shall be preceded by an escort vehicle with height pole, which shall precede the permittee to provide warning to traffic and advise permittee of hazardous conditions.

Oklahoma:

Weight requiring independent route review is dependent upon the configuration of the vehicle(s) and specific route.

- 6.01 Scope:** The provisions of this chapter apply to allowed dimensions of manufactured housing and to minimum requirements for the tow vehicles used for transport.

It is further intended that the guidelines provided in this section will form the basis for WASHTO interstate permitting agreements for manufactured housing.

6.02 Manufactured Housing Recommended for Interstate Permit Agreements:

6.02.1 Width: Maximum width of 14 feet plus 2 feet allowed for eaves.

6.02.2 Length:

1. Maximum length for a housing unit, including tongue – 80 feet.
2. Maximum combined length for housing unit and tow vehicle – 90 feet.

6.02.3 Height: Maximum height of housing unit in transport – 14 feet – limited to the vertical clearance of the route.

6.02.4 Axles: Axles must be in sufficient number to support enough tires to comply with the tire loading requirements in this section.

6.02.5 Brakes: Brakes must be designed and installed to activate if the housing unit accidentally breaks away from the towing vehicle. Brakes must operational on all wheels.

6.02.6 Tire Loadings: Tire loadings are dependent on when the housing unit was manufactured and must comply as follows:

1. **Tire loadings** on housing units manufactured **after January 1, 2002** (labeled pursuant to 24 CFR 3282.362 (c)(2)(i)) may not exceed the manufacturers rating as marked on the sidewall. In the absence of a sidewall marking, the tires on the housing unit must comply with the load rating specified in any of the publications of any organization listed in the Federal Motor carrier Safety Standard (FMCSS) No. 119 (49 CFR 571.119, S5.1 (b)). Housing units with no verifiable date of manufacture must also not exceed the manufacturers tire load rating.
2. **Tire loadings** on housing units manufactured **before January 1, 2002** (labeled pursuant to 24 CFR 3282.362 (c)(2)(i)) must not exceed more than 18 percent above the manufacturer's rating as marked on the sidewall. In the absence of a sidewall marking, the tires on the housing unit must not exceed eighteen percent above the load rating specified in any of the publications of any organization listed in the Federal Motor carrier Safety Standard (FMCSS) No. 119 (49 CFR 571.119, S5.1 (b)). Housing units transported on tires overloaded by nine percent or more must not be moved at speeds exceeding fifty miles per hour (50 mph or 80 km/hr).

- 6.03 Manufactured Housing With a Base in Excess of 14 Feet Wide:** Housing units in excess of the dimensional criteria recommended for interstate permitting agreements are subject to the criteria of the individual states.

6.04 Tow Vehicles Requirements:

6.04.1 Equipped with at least one drive axle with dual wheels.

6.04.2 Wheelbase of at least 100 inches.

6.04.3 Have a minimum combined gross axle weight rating, assigned by the manufacturer, to meet the requirements of the tow vehicle plus housing unit.

6.04.3 Have sufficient engine horsepower to maintain posted speed limits or trucks on the interstate, with the acknowledgment that each state retains the right to regulate the speed of a transported manufactured housing unit.

6.05 Time of Travel: Movement shall be allowed in accordance with the provisions of Chapter 6.

6.06 Lights, Signs, and Pilot/Escorts: Lights, signs and the use of pilot/escort vehicles shall meet the provisions of Chapters 7 and 8.

Chapter 7.00

Lighting, Flagging, Signing, and Time of Movement Requirements

7.01 Scope: The provisions of this chapter are intended to supplement legal requirements for motor vehicles and apply to vehicles transporting oversize nondivisible loads, including manufactured housing.

7.02 Lights, Flags, and Signs:

7.02.1 Lighting Requirements for Oversize Loads Traveling After Dark: Those overdimensional loads traveling during hours of darkness shall be required to display lights to mark the extremities of the vehicle and/or load, and shall be, in addition to those clearance lights, required on legal size vehicles when traveling at night.

1. Standards for Lights on Oversize Vehicles and/or Loads

- a. Lights are only required on those vehicles traveling after dark.
(Dark is defined as $1/2$ hour after sunset to $1/2$ hour before sunrise.)
- b. The lights must be visible from a minimum of 500 feet.
- c. The lights shall be steady burning.
- d. The color of the lights shall be as follows:
 - (1) Lights visible from the front of the vehicle and/or load and the extremities in the middle or near the front of the vehicle and/or load shall be amber.
 - (2) Lights visible from the back of the vehicle and/or load and the extremities near the back of the vehicle and/or load shall be red.

2. Standards for Lights on Rear Overhang

- a. Lights are required when rear overhang exceeds the end of the trailer by 4 feet or more.
 - (1) If the overhang is 2 feet wide or less, only one light is required on the end of the load.
 - (2) If the overhang is over 2 feet wide, two lights are required on the end of the load to show the maximum width of the overhang.

*See diagrams at end of chapter.

3. Standards for Warning Lights on Towing Vehicles

- a. Amber flashing lights displayed on a towing vehicle operating at night, shall be mounted above the cab and meet the following:
 - (1) Rotating or flashing beacon visible from a minimum of 500 feet.

7.02.2 Flagging Requirements for Oversize Loads:

1. **Warning Flags.** All overwidth and overlength vehicles and/or loads, excluding longer combination vehicles, shall be marked by warning flags meeting the following:
 - a. Warning flags are required on all overwidth loads and loads with rear overhang of 4 feet or more from the end of the trailer.
 - b. Size – 12 inches by 12 inches.
 - c. Color – Solid Red or Fluorescent Orange.
 - d. Placement of Flags:
 - (1) On overwidth loads, flags shall be placed at the four corners and/or extremities of the vehicle and/or load.

Front – Fastened to each front corner of the vehicle and/or load if it exceeds legal width.

Rear – Fastened to each corner of the extremities of the vehicle and/or load at the rearmost part of the vehicle or load if it exceeds legal width.

Side – Fastened to mark any extremity of size if wider than the front or the rear (see examples).
 - (2) If rear overhang exceeds the end of the trailer by 4 feet or more, one flag is required at the extreme rear, if the width of the projection is 2 feet wide or less. If the projection exceeds 2 feet in width, then two flags are required at the extreme rear to indicate the maximum width.

*See diagrams at end of chapter.

7.02.3 Signing Requirements for Oversize Loads: “OVERSIZE LOAD” signs shall meet the following specifications:

1. **Dimensions** – 18 inches high by 7 feet wide, letter height 10 inches, letter type Standard Series C, stroke width $1\frac{5}{8}$ inch, black letters on yellow background.
2. **Displaying Signs** – “OVERSIZE LOAD” signs shall be displayed on the front or roofline of the towing vehicle and the rear of the oversize load.
3. **When Signs Are Required** – “OVERSIZE LOAD” signs shall be required on all vehicles and/or loads exceeding legal width. Signs shall not be displayed when the vehicle is empty and of legal dimensions.

7.03 Conditions Requiring Escorts: One escort in advance of the extra-legal vehicle is required for the following listed conditions:

On two-lane, two-way roadways when:

- The load exceeds 12 feet in width, but is 14 feet or less in width.
- The load exceeds 105 feet in length.

On four-lane and divided roadways when:

- The load exceeds 14 feet in width.
- The load exceeds 120 feet in length.

On all roadways when:

- The load overhang exceeds 20 feet.





Two pilot/escorts, one in advance and one following the extra-legal vehicle, are required for the following listed condition:

On two-lane, two-way roadways when:




- The load exceeds 14 feet in width, but is 16 feet or less in width.

7.04 Time of Movement: Movement shall be allowed any day during daylight hours ($1/2$ hour before sunrise to $1/2$ hour after sunset) except the day before the holiday, the holiday, and the day after the holiday for those national holidays listed below:





New Years Day	Labor Day
Memorial Day	Thanksgiving Day
Independence Day	Christmas Day





EXAMPLES FOR WARNING LIGHTS ON OVERWIDTH LOADS



EXAMPLES FOR RED WARNING LIGHTS ON OVERLENGTH LOADS WITH A REAR END OVERHANG OF FOUR FEET OR MORE FROM END OF TRAILER



RED OF FLORESCENT ORANGE WARNING FLAGS ON OVERWIDTH LOADS



OR LOADS WITH A REAR END OVERHANG OF FOUR FEET OR MORE FROM END OF TRAILER

8.01 Scope: The contents of this chapter are designed to give any jurisdiction the tools necessary to regulate the use of pilot/escort vehicles. Included are recommended minimum requirements for pilot/escort vehicle operators and equipment. Use of these minimum requirements will help assure reciprocity with other jurisdictions that have used these recommendations as their basis for regulation.

8.02 Pilot/Escort Vehicle Operator Certification:

8.02.1 The operator of a pilot/escort vehicle must obtain and maintain certification as provided in this chapter to be authorized to escort an extra-legal vehicle or load on a state highway. The permittee of the extra-legal vehicle or load shall be responsible to inspect a pilot/escort vehicle operator's certification to ensure that it is valid and current. To obtain a certification, the operator must:

1. Submit an application for certification to the department, in the form required by the department. The application must contain all required information and documentation.
2. Receive a minimum of eight (8) hours of training specific to escort requirements, including principals of defensive driving.
3. Possess a valid motor vehicle driver's license.
4. Possess the minimum insurance as required by the state where the escort vehicle is licensed.

8.02.2 The pilot/escort vehicle certification examination will consist of pilot car escort vehicle operation requirements, including:

1. Requirements applicable to an extra-legal vehicle or load, responsibilities of the operator when escorting an extra-legal vehicle and/or load, and pilot/escort vehicle procedures, all as described in the Rules; and
2. Requirements of applicable traffic laws; and
3. Procedures for operator flagging and traffic control, as described in Section 6 E of the *Manual on Uniform Traffic Control Devices* (MUTCD), Part 6, Published September 3, 1993.

8.02.3 The certifying state may set a fee to cover administrative costs.

8.02.4 The department will grant a certificate to all persons who pass the pilot/escort vehicle certification examination and satisfy the other requirements of Section 0-2 above.

The certification must be in the possession of the pilot/escort vehicle operator at all times when the operator is escorting an extra-legal vehicle or load on a state highway. The certification shall be exclusive to the operator named in the certificate and may not be assigned or transferred.

8.02.5 The term of the certification shall be for a maximum period of four years, subject to Section 0-7 below, and shall expire automatically four years after the date of issuance by the department. Operators must notify the department in writing within 30 days of any change of address or name. Upon expiration of the certification, an operator must again comply with the requirements of Section 0-2 of the Rules before the department will issue a new certificate.

8.02.6 The certification shall be deemed automatically canceled, suspended, or revoked for:

1. Failure to satisfy the requirements of Section 0-2 above, or failure to give the required or correct information on the application for certification as a pilot/escort vehicle operator, or the commission of any fraud in making the application.
2. Violation of rules established by the certifying state.
3. Failure to notify the department of any cancellation, suspension, or revocation of the operator's motor vehicle driver's license by the "DMV" within five working days of the operator's receipt of notice of the same.
4. Conduct while operating a motor vehicle or a pilot/escort vehicle, which, as determined by the department, threatens the public safety or welfare of highway users or creates unreasonable interference with the efficient movement of traffic.
5. Allowing or permitting an uncertified person to operate a pilot/escort vehicle under the operator's supervision or direction.

8.03 Pilot/Escort Vehicle Operational Procedures:

8.03.1 When the pilot/escort vehicle is in front of the extra-legal vehicle or load being escorted, the operator shall:

1. Warn oncoming traffic of the presence of the vehicle or load by use of signs and lights as provided in Sections 0-11 and 0-15 of the Rules.
2. Notify the driver of the extra-legal vehicle or load by two-way radio of all hazards, overhead clearances, obstructions, traffic congestion, pedestrians, and any other circumstances evident to the operator that could affect either the safe movement of the extra-legal vehicle and/or load, the safety of the traveling public, or the efficient movement of traffic in sufficient time for the driver of the extra-legal vehicle and/or load to take remedial action, as necessary.
3. To the extent necessary, locate safe places (if available) adjacent to the highway and notify the driver of the extra-legal vehicle or load thereof to allow the extra-legal vehicle and/or load and the pilot/escort vehicle(s) to clear the highway, so that following traffic can safely pass or for any other reasons necessary to protect public safety and the efficient movement of traffic.
4. Be far enough in front of the extra-legal vehicle and/or load to signal oncoming motorists to stop in a timely manner, or as specified by local jurisdiction, before such motorists enter any narrow structures or other restrictions on the highway to permit the safe passage of the vehicle or load.

8.03.2 When the pilot/escort vehicle is behind the extra-legal vehicle or load, the operator shall:

1. Warn traffic approaching from the rear of the presence of the extra-legal vehicle or load ahead, by use of signs and lights as provided in Section 0-11 and 0-15 of the Rules.
 2. Notify the driver of the extra-legal vehicle or load by two-way radio of flat tires or other problems with the extra-legal vehicle and/or load, objects coming loose from the extra-legal vehicle and/or load, other traffic approaching or passing the extra-legal vehicle and/or load, and any other circumstances evident to the operator that could affect either the safe movement of the extra-legal vehicle and/or load, the safety of the traveling public, or the efficient movement of traffic in sufficient time for the driver of the extra-legal vehicle and/or load to take remedial action, as necessary.
 3. Notify the front pilot/escort driver and the driver of the extra-legal vehicle and/or load by two-way radio of traffic buildup and other delays to the normal flow and efficient movement of traffic caused by the movement of the extra-legal vehicle or load.
 4. Notify the driver of the vehicle and/or load by two-way radio of other vehicles attempting to pass the extra-legal vehicle and/or load.
 5. Be far enough behind the extra-legal vehicle and/or load to signal motorists following the extra-legal vehicle and/or load to slow or stop in a timely manner, or as specified by local jurisdiction, before narrow structures or other restrictions in the highway to permit the safe passage of the extra-legal vehicle and/or load.
- 8.03.3** A pilot/escort vehicle is prohibited from escorting more than one extra-legal vehicle or load at the same time, unless expressly so authorized.
- 8.03.4** A pilot/escort vehicle shall use a height pole at all times when escorting an extra-legal vehicle or load exceeding 16 feet in height, unless otherwise expressly authorized by the department on the permit. The height pole shall not extend less than 6 inches above the maximum height of the extra-legal vehicle and/or load the pilot/escort vehicle is escorting. When the pilot/escort vehicle is not escorting an extra-legal vehicle and/or load but is moving on the highway, the height pole shall be removed, tied down, or shortened to within legal limits.
- 8.03.5** Identification signs or placards shall be displayed on the pilot/escort vehicle at all times when escorting an extra-legal vehicle and/or load. The sign or placard must:
1. Appear on both sides of the pilot/escort vehicle;
 2. Be in letters that contrast sharply in color with the background on which the letters are placed;
 3. Be readily legible during daylight hours from a distance of 50 feet while the vehicle is stationary; and
 4. Be kept and maintained in a manner that retains the legibility required by subparagraph 3 of this section.
- 8.03.6** The operator of the pilot/escort vehicle shall use the pilot/escort vehicle and the equipment described herein only in compliance with the rules.

8.03.7 When a pilot/escort vehicle is not escorting an extra-legal vehicle and/or load but is moving on the highway, the signs described in Section 0-15 of the Rules shall either be removed or covered, and the flashing yellow lights described in Section 0-11 of the Rules shall not be operated.

8.03.8 In the performance of the duties required by the Rules, the operator of the pilot/escort vehicle may direct other traffic to stop, slow, or proceed in situations where such direction is necessary to allow the extra-legal vehicle or load to continue moving safely, except as provided below.

The operator of the pilot/escort vehicle shall signal the extra-legal vehicle and/or load to stop, and the extra-legal vehicle shall stop, as far off of the roadway as practicable to allow other traffic to pass the stopped extra-legal vehicle and/or load in the following situations:

1. When the extra-legal vehicle and/or load becomes disabled; or
2. When the movement of the extra-legal vehicle and/or load on a particular section of state highway presents a safety risk or unreasonably interferes with the efficient movement of other traffic, based upon such factors as the widths of the extra-legal vehicle and/or load and the roadway, volume of other traffic, visibility and limited sight distance, and mountainous terrain; or
3. When driving conditions for the extra-legal vehicle and/or load are hazardous for any other reason, including weather. When the extra-legal vehicle and/or load has been stopped pursuant to this Subsection 3, the pilot/escort operator shall then direct other traffic past the extra-legal vehicle and/or load, as necessary, until such time as the extra-legal vehicle and/or load can re-enter the roadway and continue moving without presenting a safety risk or unreasonably interfering with the efficient movement of other traffic.

When directing traffic in the situations described in this section, the operator shall comply with the flagging procedures and requirements described in Section 6 E of the M.U.T.C.D, Part 6, and Published September 3, 1993.

1. Stand outside the pilot/escort vehicle; and
2. Use the paddle signs and other equipment identified in Section 0-18.

8.03.9 The operator of the extra-legal vehicle or load and the operator of the pilot/escort vehicle shall comply with the following procedures:

1. Before trip:
 - a. Discuss aspects of the move, including the extra-legal vehicle and/or load, the route, and specific responsibilities.
 - b. Review permit conditions.
 - c. Review the permitted route.
 - d. Determine the proper position of the pilot/escort vehicle(s).
 - e. Establish particular procedures.
 - f. Check mandatory equipment.

- g. Mount signs, adjust mirrors, turn on lights.
 - h. Check each 2-way radio to ensure clear communication on a selected channel.
 - i. Verify that driver's licenses, extra-legal vehicle and/or load transport permit, and pilot car escort vehicle certification are in the possession of the operators.
 - j. Determine if additional flagpersons will be necessary and, if so, have them available.
2. During trip:
- a. Obey all traffic laws.
 - b. Maintain proper distance between the extra-legal vehicle and/or load and the pilot/escort vehicle:
 - (1) Do not follow or precede more closely than is reasonably prudent, considering the speed of the extra-legal vehicle and/or load, other traffic, and highway conditions.
 - (2) Do not exceed $\frac{1}{2}$ -mile distance between extra-legal vehicle and/or load and the pilot/escort vehicle to maintain radio contact.
 - (3) Be close enough to warn other traffic of extra-legal vehicle or load.
3. Traffic lights:
- a. If the pilot/escort vehicle goes through a traffic light but the extra-legal vehicle and/or load does not, then the pilot/escort vehicle must pull over to the right side of the highway, where practicable, to wait for the extra-legal vehicle and/or load.
 - b. If the extra-legal vehicle and/or load goes through the traffic light but the pilot/escort vehicle does not, then the extra-legal vehicle and/or load must continue and the pilot/escort vehicle must catch up when possible.

8.04 Pilot/Escort Vehicle and Equipment Requirements:

- 8.04.1** The pilot/escort vehicle operator shall ensure that the pilot/escort vehicle is in safe operating condition at all times when the pilot/escort vehicle is escorting an extra-legal vehicle or load.
- 8.04.2** A pilot/escort vehicle shall, in addition to any other equipment required by the traffic laws, be equipped with at least one, but not more than three, flashing yellow lights, as defined in Rules. The flashing yellow light(s) shall be visible to approaching traffic from the front and the rear of the pilot/escort vehicle.
- 8.04.3** The pilot/escort vehicle shall:
- 1. Be either a passenger car or a two-axle truck;
 - 2. Not exceed a maximum gross vehicle weight rating of 14,000 pounds;
 - 3. Be at least 60 inches wide; and
 - 4. Not exceed the legal limits of size and weight, as defined in Rules.

- 8.04.4** The pilot/escort operator shall not carry any item(s) or equipment or load in or on the pilot car escort vehicle which:
1. Exceeds the height, length, or width of the pilot car escort vehicle, or overhangs the pilot/escort vehicle, or otherwise impairs its immediate recognition as a safety pilot/escort vehicle by the motoring public; or
 2. Obstructs the view of the flashing yellow lights or the signs used by the pilot/escort vehicle; or
 3. Causes safety risks; or
 4. Otherwise impairs the performance by the operator or the pilot/escort vehicle of the duties required by the Rules.
- 8.04.5** The pilot/escort vehicle operator shall properly load and secure any item(s) or equipment or load carried by the pilot/escort vehicle to ensure compliance with the requirements of this section.
- 8.04.6** A pilot/escort vehicle shall display "Wide Load," "Long Load," or "Oversize Load" signs, as applicable, which shall be mounted above the roofline of the escort vehicle and be visible to approaching traffic from the front and the rear. All such signs shall be a minimum of 5 feet wide, 10 inches high with 1 inch wide brush stroke, black letters a minimum of 8 inches high on yellow background, or shall be a maximum of 7 feet wide, 18 inches high, with a 1.41-inch brush stroke, black letters a minimum of 10 inches high on yellow background.
- 8.04.7** The pilot/escort vehicle shall use its headlights at all times when escorting an extra-legal vehicle or load.
- 8.04.8** The pilot/escort vehicle shall be equipped with two-way radio facilities capable of providing reliable voice communication both ways between the driver of the extra-legal vehicle and/or load and the driver of the pilot/escort vehicle at all times when the extra-legal vehicle and/or load is in motion on a state highway.
- 8.04.9** A pilot/escort vehicle shall carry the following items of equipment at all times when escorting an extra-legal vehicle or load:
1. Standard 18 inch STOP & SLOW paddle sign.
 2. Three bi-directional emergency reflective triangles.
 3. A minimum of one 5 pound B,C, fire extinguisher.
 4. A reflectorized orange vest, shirt, or jacket, which must be worn by the operator while directing traffic.
 5. An orange or white hard hat, which must be worn by the operator when out of the vehicle.
 6. Two additional signs, as described in Section 0-15.
 7. A height measuring device which is nonconductive and nondestructive to overhead clearances, when required by the terms of the permit or regulations.
 8. A first aid kit.
 9. A flashlight with a red cone and extra batteries.

- 9.01 Scope:** The provisions of this chapter apply to LCVs. It is intended that each state, which allows LCVs, will designate highway systems for LCV operations.

Further, the provisions of this chapter are intended as a uniformity guide for those WASHTO states which presently provide for some type of LCV operations. The inclusion of this chapter in the guide should not be interpreted as a WASHTO endorsement of LCV operations for all WASHTO states.

- 9.02 Rocky Mountain Doubles:** See figure on page 42.

9.02.1 Combination Length: No maximum.

9.02.2 Combination Trailer Length: 81 feet maximum.

9.02.3 Trailer Length: 48 feet maximum.

9.02.4 Optional Dimensions: Other truck tractor double trailer combinations should be allowed which provide maximum off track and other operational characteristics similar to or better than a rocky mountain doubles combination including trailers of 48 feet and $28\frac{1}{2}$ feet within 81 feet combination trailer length.

- 9.03 Turnpike Doubles:** See figure on page 42.

9.03.1 Combination Length: 110 feet maximum.

9.03.2 Trailer Combination Length: 95 feet maximum.

9.03.3 Trailer Length: 45 feet maximum.

9.03.4 Optional Dimensions: Other truck tractor double trailer combinations should be allowed which provide maximum off track and other operational characteristics similar to or better than a turnpike doubles combination with twin 45 feet trailers.

- 9.04 Triple Trailers:** See figure on page 42.

9.04.1 Combination Length: No maximum.

9.04.2 Combination Trailer Length: 95 feet maximum.

9.04.3 Trailer Length: $28\frac{1}{2}$ feet maximum.

- 9.05 Maximum Weights:** Allowable axle group weights and gross vehicle weight of LCVs, should be determined in accordance with Federal Bridge Formula "B" (refer to Chapter 2.00, Section 2.05.2). Maximum gross vehicle weight should be a minimum of 105,500 pounds and a maximum of 129,000 pounds.

- 9.06 Permits:** The authority to operate LCVs should be by permit, in accordance with the LCV Model Permit Provisions contained herein.

- 9.07 LCV General Permit Provisions:**

1. The driver and company shall be jointly responsible for meeting the permit requirements.
2. No other trailer configurations or multiple trailer combinations needing a permit may be operated under this permit unless these are specifically listed on the permit or otherwise authorized.

3. This permit requires that the permittee have an established safety program. In addition, the permittee must not have an unsafe or unsatisfactory USDOT or other safety rating from any state or province in which he operates. This permit is automatically void if the operator incurs an unsatisfactory rating. The permit will be reinstated when proof has been submitted to the permit authority that the motor carrier has been officially notified by the USDOT, the state or province giving the unsafe or unsatisfactory safety rating that a satisfactory rating has been restored.
4. The permit is valid for those routes designated on the permit. No authority is given to travel on routes other than those listed.
5. This permit may be suspended or revoked for failure to comply with any of the provisions or conditions of this permit. The motor carrier and driver, must comply with all of the motor vehicle laws and the latest motor carrier safety regulations, issued by the USDOT. Traveling faster than the posted speed limit is a permit violation.

9.08 LCV Equipment: In addition to the requirements of Section 1, the following rules and regulations also apply:

1. All trucks and truck tractors shall be powered to provide adequate acceleration and hill-climbing ability under normal operating conditions to allow speeds compatible with other traffic. The ability to maintain a minimum speed of 20 mph while climbing grades is required unless the state or province highway engineer authorizes exemption for a specific grade.
2. Tires: Each axle must have tires of the same size and construction. Tires must be properly inflated for the load to be carried. In no event shall any tire, wheel, or rim exceed the manufacturer's maximum load-carrying limit. A vehicle designed for dual tires may not have the dual tires replaced by a single tire. No single tires on single-axle configurations, except the steering axle, are allowed.
3. All hitch connections must be of a no-slack type, which must be visible and operating. All drawbars, pickup plates, and fifth wheels must be rated to exceed the weight carried. Any kingpin must be the solid type and permanently fastened.
4. All braking systems must comply with state, province, and federal requirements. In addition, fast air transmission and release valves must be provided for all trailers, semitrailers, and converter dollies.
5. Mud flaps or splashguards must be antisail types. Mudguards are required behind each nonsteering axle or set of axles.
6. If a sign is required, it shall read "LONG LOAD" and be at least 7 feet long and 18 inches high. The background shall be yellow with black lettering. Letters shall be at least 10 inches high with a 1.41-inch brush stroke.

Note: If Series E modified letters are used, the brush stroke shall be 2 inches.

9.09 LCV Operational Requirements:


1. Vehicles authorized under this permit must stay in the right lane when practical unless they are in the act of passing.
2. The minimum distance between the permitted vehicle and other trucks shall be at least 100 feet for each 10-mph of speed, except when passing.
3. When the speed of the vehicle drops to 20 mph less than the posted truck limit when climbing grades, the driver must use emergency flashers to notify the passing traffic that they are approaching a vehicle traveling substantially slower than the rest of the traffic.
4. Load Sequence: In no case shall any lighter trailer or semitrailer be placed ahead of a heavier trailer or semitrailer which carries more than 4,000 pounds more than a leading trailer(s). The heaviest trailer or semitrailer shall be placed in front, the lightest in the rear.
5. The operator shall turn on headlights whenever the windshield wipers are in operation or any other time when visibility is poor.
6. Extreme caution in the operation of a motor vehicle shall be exercised when hazardous conditions such as those caused by snow, ice, sleet, fog, mist rain, dust, or smoke adversely affect visibility or traction. Speed shall be reduced when such conditions exist. When conditions become sufficiently dangerous, the company or the operator shall discontinue operations, and operations shall not be resumed until the vehicle can be safely operated. The state may restrict or prohibit operations during periods when, in the state's judgment, traffic, weather, or other safety conditions make such operations unsafe or inadvisable.

9.10 LCV Driver Requirements:


1. All LCV drivers must have a current Commercial Driver's License with the following endorsements: doubles/triples and air brake equipment.
2. LCV drivers and all other individuals or companies operating LCVs must comply with Part 391, Qualifications of Drivers of the Federal Motor Carrier Safety Regulations (FMCSR). Driver exemptions as set forth in sections 391.21 and 391.67 of the FMCSR shall not apply to LCV drivers.
3. All LCV drivers must have a minimum of two years' "linehaul" driving experience driving truck combinations. LCV triple drivers must have a minimum of two years' "line-haul" driving experience driving double-trailer combinations.
4. An LCV driver must be a regularly employed driver and supervised by the company or individual holding the LCV permit.
5. An LCV driver must have had no suspension or revocation of driving privileges in any state or province during the past 24 months where such suspension arose out of operations of a commercial motor vehicle.

Longer Combination Vehicles


ROCKY MOUNTAIN DOUBLES



TURNPIKE DOUBLES



TRIPLE TRAILERS



10.01 Scope: It is the intent of this chapter to set forth some standards for permit programs, permit form designs, and methods of securing and paying for permits.

Adoption of these standards by the various WASHTO states should accomplish two objectives. The first to provide greater uniformity in the permit process which would aid industry and the second to provide a basis for eventual universal interstate permit agreements between the WASHTO states which would aid both industry and state administrations.

10.02 Single Trip Permits: All WASHTO states should provide for single trip permits.

10.03 Permit Forms: The WASHTO permit form (see figure on pages 44 and 45) should be used as a guide by individual states in developing new permit forms.

10.04 Route Identification: Routes shall be specified on each single trip permit.

10.05 Methods of Securing Permits: States should accept permit applications in person, by telephone, by wire, fax, and mail.

10.06 Methods of Payment: States should accept credit cards for payment of permit fees.

10.07 Sample Oversize/Overheight Permit:**SPECIAL MOTOR VEHICLE
OVERSIZE/OVERWEIGHT**

State Logo

Permit Number:

Start :

Expires

Office:

Agent Name

Issued:

Report #:

Original Permit #:

Suspense #:

Company Name:

Address:

Total Fee :

Power Unit No:

License:

Power Unit Axles:

Miles

VIN

Trailer Unit Axles:

Km:

Lic State

Year:

Make:

Load/ Transportation Item:

Note:

From:

To:

Routing:

Max Weights

LB

KG

Max Dimensions

FT

Meters

Gross:

Width:

Legal:

Height:

Excess Gross:

Overall Length:

Gross Axle:

Trlr/Load Length:

Legal Axle:

Front Overhang:

Excess Axle:

Rear Overhang:

Special Conditions :

READ THIS BEFORE SIGNING

The Undersigned permittee acknowledges that the permit has been issued with the specific understanding that all applicable Washington State Laws, Administrative Codes, regulations and conditions will be complied with, and that the information contained herein is true and correct. Undersigned permittee must be contact local jurisdiction when not operating on state highways.

SIGNED X _____**PERMIT NOT VALID UNLESS SIGNED BY PERMITTEE VIOLATION OF SPECIAL PERMITS - PENALTY :**

For failure to obtain, misrepresentation, or violation of special permits, State law provides for a fine, confiscation and suspension of permit without refund. No refunds after the start of the effective dates.

**SPECIAL MOTOR VEHICLE
OVERSIZE/OVERWEIGHT**

SPECIAL MOTOR VEHICLE PERMIT

Permit Number

Start Date

Expire Date

Route Nbr

MP From

MP To

**ATTACHMENT
ROUTE FOR THIS PERMIT**

Restriction Comments

Chapter 11.00

Retractable or Variable Load Suspension Axles

- 11.01 Scope:** The purpose of this chapter is intended to promote safety and reduce the pavement damage resulting from operating with retractable and/or variable load suspension (VLS) axles. The following guidelines are intended to apply to divisible loads.
- 11.02 Controls:** The up-down switch may be inside the cab. The pressure regulator valve shall be positioned outside of the cab and be inaccessible from the driver's compartment.
- 11.03 Axle Rating:** Axles shall not exceed their design load capacity as indicated by an attached data plate or written certification from a vendor.
- 11.04 Tires:** Tires shall not exceed their rated load capacity (sidewall) rating as specified by the manufacturer.

Appendices

	Page
Appendix A	Vehicles in Regular Operation: National Network
	(U.S. Measurement) 52
	(Metric Measurement) 54
Appendix B	Vehicles in Regular Operation: Non-national Network
	(U.S. Measurement) 56
	(Metric Measurement) 58
Appendix C	Nondivisible Load Permits: National Network and Other Designated Highways
	(U.S. Measurement) 60
	(Metric Measurement) 62
Appendix D	Transporting Manufactured Housing: National Network and Other Designated Highways
	(U.S. Measurement) 64
	(Metric Measurement) 66
Appendix E	Pilot/Escort Vehicles: National Network and Other Designated Highways
	(U.S. Measurement) 68
	(Metric Measurement) 70
Appendix F	Longer Combination Vehicles
	(U.S. Measurement) 72
	(Metric Measurement) 74
Appendix G	Additional Longer Combination Vehicles
	(U.S. Measurement) 76
	(Metric Measurement) 78
Appendix H	Canadian Vehicle Weight Limits 80
Appendix I	Canadian Dimension Limits 82
Appendix J	Mexican Vehicle Weight Limits 84
Appendix K	Mexican Vehicle Dimension Limits 92
Appendix L	WASHTO Resolution 13-04 100

Appendix A

Vehicles in Regular Operation: National Network* (U.S. Measurement)

	AK	AZ	CA	CO	HI	ID	MT	NE
Height	14'	14'	14'	13'	14'	14'	14'	14'6"
Width	8'6"	8'6"	8'6" ^H	8'6"	9'	8'6"	8'6"	8'6"
Single Unit Length	45'	40'	40' ^H	45'	45'	45'	55'	40'
Truck-Trailer								
Overall Length	90'		65' ^H	70'	65'	75'	75'	65'
Tractor-Semitrailer								
Overall Length	NS	NS	Unlimited ^H		Unlimited	NS		
Trailer Length	53'	57'6"	48'/53' ^H	57'4"		53'	53'	53'
Kingpin Distance	41'	NS	Unlimtd/40' ^H			NS		
Tractor-Semitrailer-Trailer (Doubles)								
Overall Length	120'	NS	Unlimited ^H	^A	Unlimited	NS		
Combined trailer Length	95'	NS	NS			68'	61'	65'
Individual Trailer Length	53'	28'6"	28'6" ^H	28'6"		NS	28'6"	
Weights/Inch of Tire Width (In lbs)								
Steering Axle	600#	NS	620			600#	^F	
Other Axles With Single Tires	550#		620			600#	^G	
Other Axles Without Single Tires			620					
Axle Weights (In 1000 lbs)								
Steering Axle	20	20	20 ^H	20		20	20	20
Single Axle	20	20	20 ^H	20	22.5	20	20	20
Tandem Axle	38	34	34 ^H	36	34	34 ^B	34	34
Gross Weight (In 1000 lbs)								
Interstate Routes	Uncapped	80	80	80	80	80 ^C	Uncapped	80
Non-Interstate Routes			80	85		105.5		95
Federal Bridge Formula?	Yes	Yes	Yes ^H	Yes	Yes	Yes	Yes	Yes

Footnotes:

NA Not Available

NS..... Not Specified

A None unless semitrailer or trailer exceeds 28'6"

* And designated access routes

B 37,800 for special agricultural and mining products on interstate up to GVW 79,000 lbs

C By permit on Interstate over 80,000 GVW

D Not to exceed 550 lbs per inch width of tire

E Single trailers permitted to 56', double trailers to 68'

F Manufacturers tire rating

G 500 lbs on wide base tires only

H With exceptions

I 48' semitrailer, 40' trailer

NV	NM	ND	OK	OR	SD	TX	UT	WA	WY	WASHTO
14'	14'	14'	13'6"	14'	14'	14'	14'	14'	14'	14'
8'6"	8'6"	8'6"	8'6"	8'6"	8'6"	8'6"	8'6"	8'6"	8'6"	8'6"
40'	40'	50'	45'	40'	45'	45'	45'	40'	60'	45'
70'	65'	75'	70'	75'	80'	65'	65'	75'	85'	70'
	65'	Unlimited							NS	65'
53'	57'6"	53'	59'6"	53'	53'	59'	48'	53' ^E	60'	48'
						41'		NS		
70' ^A	65'	Unlimited							NS	
N/A	28'6"		110'	68'	81'6"		61'	61' ^E	81'	61'
28'6"		53'	53'	40'	45'	28'6"		53'	^I	
600#	600#	550#		600#	600#	^F	^F	600#	750#	600#
500#	600#	550#		600#	500#	^F	600#	500#	600#	500#
	550#									
	20	20	20	20	20	20	20	20	20	
20	21.6	20	20	20	20	20	20	20	20	20
34	34.32	34	34	34	34	34	34	34	36	34
80	86.4	80 ^C	80 ^C	80	Uncapped ^C	80	80	105.5	117	80
		105.5	90						117	
Yes	Modified	Yes	Yes	Modified	Yes	Yes	Yes	Yes	Yes MOD	Yes

Appendix A

Vehicles in Regular Operation: National Network* (Metric Measurement)

	AK	AZ	CA	CO	HI	ID	MT	NE
Height	4.26 m	4.26 m	4.26 m	3.96 m	4.26 m	4.26 m	4.26 m	4.41 m
Width	2.59 m	2.59 m	2.59 m ^H	2.59 m	2.74 m	2.59 m	2.59 m	2.59 m
Single Unit Length	13.71 m	12.19 m	12.19 m ^H	13.71 m	13.71 m	13.71 m	16.76 m	12.19 m
Truck-Trailer								
Overall Length	27.43 m		19.81 m ^H	21.33 m	19.81 m	22.86 m	22.86 m	19.81 m
Tractor-Semitrailer								
Overall Length		NS	Unlimited ^H		Unlimited	NS		
Trailer Length	16.15 m	17.52 m	14.63m/16.1m ^H	17.47 m		16.15 m	16.15 m	16.15 m
Kingpin Distance	12.49 m	NS	Unlimited/12.19m ^H			NS		
Tractor-Semitrailer-Trailer								
(Doubles)								
Overall Length	36.57 m	NS	Unlimited ^H		Unlimited	NS		
Combined trailer Length	28.95 m	NS	NS			20.72 m	18.59 m	19.81 m
Individual Trailer Length	16.15 m	8.68 m	8.68 m ^H	8.68 m		NS	8.68 m	
Weights (kg)/Inch of Tire Width								
Steering Axle	272	NS	281			272	^F	
Other Axles With Single Tires	249		281			272	^G	
Other Axles Without Single Tires			281					
Axle Weights (kg)								
Steering Axle	9,071	9,071	9,071 ^H	9,071		9,071	^F	
Single Axle	9,071	9,071	9,071 ^H	9,071	10,205	9,071	9,071	9,071
Tandem Axle	17,236	15,422	15,422 ^H	16,329	15,422	15,422 ^B	15,422	15,422
Gross Weight (kg)								
Interstate Routes	Uncapped	36,287	36,287	36,287	36,287	47,853 ^C	Uncapped	36,287
Non-Interstate Routes			36,287	38,556				43,091
Federal Bridge Formula?	Yes	Yes	Yes ^H	Yes	Yes	Yes	Yes	Yes

Footnotes:

NA Not Available

NS..... Not Specified

m meters

kg kilograms

A None unless semitrailer or trailer exceeds 8.68 m

* And designated access routes

B 17,145 kg for special agricultural and mining products on interstate up to GVW 35,833 kg

C By permit on Interstate over 36,287 kg GVW

D Not to exceed 249 kg per inch width of tire

E Single trailers permitted to 17.07 m, double trailers to 20.73 m

F Manufacturers tire rating

G 226 kg on wide base tires only

H With exceptions

I 14.63 m semitrailer, 12.19 m trailer

NV	NM	ND	OK	OR	SD	TX	UT	WA	WY	WASHTO
4.26 m	4.26 m	4.26 m	4.11 m	4.26 m	4.26 m	4.26 m	4.26 m	4.26 m	4.26 m	4.26 m
2.59 m	2.59 m	2.59 m	2.59 m	2.59 m	2.59 m	2.59 m	2.59 m	2.59 m	2.59 m	2.59 m
12.19 m	12.19 m	15.24 m	13.71 m	12.19 m	13.71 m	13.71 m	13.71 m	12.19 m	18.28 m	13.71 m
21.33 m	19.81 m	22.86 m	21.33 m	22.86 m	24.38 m	19.81 m	19.81 m	22.86 m	25.90 m	21.33 m
	19.81 m	Unlimited							NS	19.81 m
16.15 m	17.52 m	16.15 m	18.13 m	16.15 m	16.15 m	17.98 m	14.63 m	16.15 m ^E	18.28 m	14.63 m
						12.49 m		NS		
21.33 m	19.81 m	Unlimited							NS	
N/A	8.68 m		33.52 m	20.72 m	24.84 m		18.59 m	18.59 m ^E	24.68 m	18.59 m
8.68 m		16.15 m	16.15 m	12.19 m	13.71 m	8.68 m		16.15 m	^I	
272	272	249		272	272	^F	^F	272	340	272
226	272	249		272	226	^F	272	226	272	226
	249									
	9,071	9,071	9,071	9,071	9,071	9,071	9,071	9,071	9,071	
9,071	9,797	9,071	9,071	9,071	9,071	9,071	9,071	9,071	9,071	9,071
15,422	15,567	15,422	15,422	15,422	15,422	15,422	15,422	15,422	16,329	15,422
36,287	39,190	36,287 ^C	36,287 ^C	36,287	36,287 ^C	36,287	36,287	47,853	53,070	36,287
		47,853	40,824						53,070	
Yes	Modified	Yes	Yes	Modified	Yes	Yes	Yes	Yes	Yes MOD	Yes

Appendix B Vehicles in Regular Operation: Non-national Network (U.S. Measurement)

Vehicle & Load Dimensions	AK	AZ	CA	CO	HI	ID	MT	NE
Height	14'	14'	14'	13'	14'	14'	14'	14'6"
Width	8'6"	8'6"	8'6" ^R	8'6"	9'	8'6"	8'6"	8'6"
Single Unit Length	45'	40'	40' ^R	45'	45'	45'	55'	40'
Truck-Trailer								
Overall Length	75'		65' ^R	70'	65'	75'	75'	65'
Tractor-Semitrailer								
Overall Length	75'	65' ^B	65' ^R	^C	65'	65' ^O		
Trailer Length	48'	53'	Unlimited	57'4"		48'	53'	53'
Kingpin Distance	NS	NS	40'			NS		
Tractor-Semitrailer-Trailer								
(Doubles)								
Overall Length	75'	NS	75'	^F	65'	75' ^G		
Combined trailer Length		NS	N/A			61'	61'	65'
Individual Trailer Length	48'	28'6"	28'6" ^R	28'6"		NS	28'6"	
Weights/Inch of Tire Width								
Steering Axle	600#	NS	620		NS	600#	^P	
Other Axles With Single Tires	550#		620		NS	600#	^Q	
Other Axles Without Single Tires					NS			
Axle Weights (In 1000 lbs)								
Steering Axle	20	20	20	20	20	20	^F	20
Single Axle	20	20	20	20	22.5	20	20	20
Tandem Axle	38	34	34	40' ^I	34	37.8	34	34
Gross Weight (In 1000 lbs)								
Non-Interstate Routes	Uncapped	80	80	85	88	105.5	Uncapped	95
Federal Bridge Formula?	Yes	Yes ^R	Yes ^R	^I	^J	Yes	Yes	Yes

Footnotes:

NS..... Not Specified

B None unless the semitrailer exceeds 53'

C None unless the semitrailer exceeds 57'4"

D Single trailers permitted to 56', double trailers to 68'

E Some Non-National Network highways are 95' and 110'

F None unless semitrailer or trailer exceeds 28'6"

G None unless trailer combination length is exceeded

H 48' semitrailer, 40' trailer

I Formula: $W = 1000 \times (L+40)$

J Formula: $W = 900 \times (L+40)$ on non-interstate

O On designated routes

P Manufacturers tire rating

Q 500 lbs wide base tires only

R With exceptions

S Based on tire size

T 80,000 lbs on posted highways

NV	NM	ND	OK	OR	SD	TX	UT	WA	WY	WASHTO
14'	14'	14'	13'6"	14'	14'	14'	14'	14'	14'	14'
8'6"	8'6"	8'6"	8'6"	8'6"	8'6"	8'6"	8'6"	8'6"	8'6"	8'6"
40'	40'	50'	45'	40'	45'	45'	45'	40'	60'	45'
70'	65'	75' ^E	70'	75'	80'	65'	65'	75'	85'	70'
70'	65' ^D	75' ^E		60'					NS	65'
53'	57'6"	53'	53'		53'	59'	48'	53'	60'	48'
	NS					41'		NS		
70' ^F	65' ^D	75' ^E		75'					NS	
	28'6"	NS	110'		81'6"		61'	61' ^D	81'	61'
28'6"		53'	53'	40'	45'	28'6"	28'6"	53'	^H	
600#	600#	550#		600#	600#	^P	^P	600#	750#	600#
500#	600#	550#		600#	500#	^P	600#	500#	600#	500#
		550#								
^S	20	20	20	20	20	20	20	20	20	
20	21.6	20	20	20	20	20	20	20	20	20
34	34.32	34	34	34	34	34	34	34	36	34
80	86.4	105.5 ^T	90	80	Uncapped	80	80	105.5	117	80
Yes	Modified	Yes	Modified	Modified	Yes	Yes	Yes	Yes	Yes MOD	Yes

Appendix B

Vehicles in Regular Operation: Non-national Network (Metric Measurement)

	AK	AZ	CA	CO	HI	ID	MT	NE
Height	4.26 m	4.26 m	4.26 m	3.96 m	4.26 m	4.26 m	4.26 m	4.41 m
Width	2.59 m	2.59 m	2.59 m ^R	2.59 m	2.74 m	2.59 m	2.59 m	2.59 m
Single Unit Length	13.71 m	12.19 m	12.19 m ^R	13.71 m	13.71 m	13.71 m	16.76 m	12.19 m
Truck-Trailer								
Overall Length	22.86 m		19.81 m ^R	21.33 m	19.81 m	22.86 m	22.86 m	19.81 m
Tractor-Semitrailer								
Overall Length	22.86 m	19.81 m ^B	19.81 m ^R	^C	19.81 m	19.81 m ^O		
Trailer Length	14.63 m	16.51 m	Unlimited	17.47 m		14.63 m	16.51 m	16.15 m
Kingpin Distance	NS	NS	12.19 m			NS		
Tractor-Semitrailer-Trailer (Doubles)								
Overall Length	22.86 m	NS	22.86 m	^F	19.81 m	22.86 m ^G		
Combined Trailer Length		NS	N/A			18.59 m		19.81 m
Individual Trailer Length	14.63 m	8.71 m	8.68 m ^R	8.68 m	8.68 m	NS	8.68 m	
Weights (kg)/Inch of Tire Width								
Steering Axle	272	NS	N/A		NS	272	^P	
Other Axles With or Without Single Tires	249		N/A		NS	272	^Q	
Axle Weights (kg)								
Steering Axle	9,071	9,071	9,071	9,071	9,071	9,071	^P	9,071
Single Axle	9,071	9,071	9,071	9,071	10,205	9,071	9,071	9,071
Tandem Axle	17,236	15,422	15,422	18,143 ^I	15,422	17,145	15,422	15,422
Gross Weight (kg)	Uncapped	36,287	36,287	38,555	39,916	47,853	Uncapped	43,091
Federal Bridge Formula?	Yes	Yes ^R	Yes ^R	^I	^J	Yes	Yes	Yes

Footnotes:

m..... meters

kg..... kilograms

B None unless the semitrailer exceeds 16.15 m

C None unless the semitrailer exceeds 17.47 m

D Single trailers permitted to 17.07 m, doubles to 20.73 m

E Some Non-National Network highways are 28.95 m and 33.52

F..... None unless semitrailer or trailer exceeds 8.68 m

G None unless trailer combination length is exceeded

H 14.63 m semitrailer, 12.19 m trailer

I Formula: $W = 453 \text{ kg} \times (L+12.19 \text{ m})$

J..... Formula: $W = 408 \text{ kg} \times (L+12.19 \text{ m})$ on non-interstate

O On designated routes

P Manufacturers tire rating

Q 226 kg wide base tires only

R With exceptions

S Based on tire size

T 36,287 kg GVW on posted state highways

NV	NM	ND	OK	OR	SD	TX	UT	WA	WY	WASHTO
4.26 m	4.26 m	4.26 m	4.11 m	4.26 m	4.26 m	4.26 m	4.26 m	4.26 m	4.26 m	4.26 m
2.59 m	2.59 m	2.59 m	2.59 m	2.59 m	2.59 m	2.59 m	2.59 m	2.59 m	2.59 m	2.59 m
12.19 m	12.19 m	15.24 m	13.71 m	12.19 m	13.71 m	13.71 m	13.71 m	12.19 m	18.28 m	13.71 m
21.33 m	19.81 m	22.86 m	21.33 m	22.86 m	24.38 m	19.81 m	19.81 m	22.86 m	25.90 m	21.33 m
21.33 m	19.81 m	22.86 m		18.28 m					NS	19.81 m
16.51 m	17.52 m	16.51 m	16.51 m		15.61 m	17.98 m	14.63 m	16.51 m ^D	18.28 m	14.63 m
		NS					12.49 m		NS	
21.33 m ^F	19.81 m ^D	22.86 m ^E		22.86 m					NS	
	8.68 m	NS	33.52 m		24.84 m		18.59 m	18.59 m ^D	24.68 m	18.59 m
8.68 m		15.61	16.15 m	12.19 m	13.71 m	8.68 m	8.68 m	16.51 m	^H	
272	272	249		272	272	^P	^P	272	340	272
226	272	249		272	226	^P	272	226	272	226
^S	9,071	9,071	9,071	9,071	9,071	9,071	9,071	9,071	9,071	
9,071	9,797	9,071	9,071	9,071	9,071	9,071	9,071	9,071	9,071	9,071
15,422	15,567	15,422	15,422	15,422	15,422	15,422	15,422	15,422	16,329	15,422
36,287	39,190	47,853 ^T	40,823	36,287	Uncapped	36,287	36,287	47,853	53,070	36,287
Yes	Modified	Yes	Modified	Modified	Yes	Yes	Yes	Yes	Yes MOD	Yes

Appendix C

Nondivisible Load Permits: National Network and Other Designated Highways (U.S. Measurement)

	AK	AZ	CA	CO	HI	ID	MT	NE
Maximum Weights								
Steering Axle:								
Lb/in tire width	NS	NS	A ^F	A	NS	600	A	NS
1000's lbs			B		23			
Single Axle (1000 lbs)	NS	28	23/30 ^F	27	23	C	C	20
Tandem (1000 lbs)	NS	46 ^C	46/60 ^F	50	34	C	C	40
Restrictions Because of:								
Darkness	NS	Yes ^F	Yes ^F	No	No	Yes	Yes	Yes
Legal Holidays	NS	Yes ^F	Yes ^F	Yes	No	Yes	Yes	Yes ^F
Weekends	NS	Yes ^F	Yes ^F	No	No	No ^F	Yes	NS
Inclement Weather	NS	Yes	Yes ^F	Yes	Yes	Yes	Yes	Yes
Escort Vehicles Required:	NS	No ^F	Yes ^I	Yes ^F	No	Yes ^F	Yes	Yes ^F

Footnotes:

NS..... Not Specified

A Manufacturers rating

B Axle rating to 20,000 lbs; tire size over 20,000 lbs

C Depends on axle spacings and route

D Escort required if bridge restrictions of center line and 5 mph apply

E 40,495 to 46,725

F..... There are exceptions

G Except under special circumstances

H Only if in combination with adjacent tandem or tridem with common suspension

I If over lane width

J..... Unless overweight only

K 10' wide x 100' long allowed on Interstate highways at night

L 12' wide allowed on Interstate at night

M Memorial Day and Labor Day

N 14' wide x 16' high x 110' long

NV	NM	ND	OK	OR	SD	TX	UT	WA	WY	WASHTO
600	600	600	13/15 ^C	600	600	650	^A	600	750	600
24	26	24		20	21.5 ^C	31	25	22	25	24
^E	46	45	40	43 ^C	52	46	50	43	55	45
No	Yes	Yes ^J	Yes	Yes ^L	No	Yes ^{KJ}	Yes	Yes ^F	No	No
No	Yes	Yes	Yes	Yes ^M	No	Yes ^N	Yes	Yes	No	No
No	Yes	Yes	Yes	Yes	No	No ^F	No	No	No	No
Yes	Yes	Yes	Yes	Yes ^M	Yes	Yes	Yes	Yes	No	No
No	Yes ^F	Yes ^F	No	No	No ^D	No ^F	Yes	Yes ^F	No ^D	No ^G

Appendix C

Nondivisible Load Permits: National Network and Other Designated Highways (Metric Measurement)

	AK	AZ	CA	CO	HI	ID	MT	NE
Maximum Weights (kg)								
Steering Axle:								
kg/in tire width	NS	NS	A ^F	A	NS	272	A	NS
Single Axle	NS	12,700	10,432 ^F 13,607 ^F	12,246	10,205	C	C	9,071
Tandem	NS	20,865	20,865 ^F 27,215 ^F	22,679	15,422	C	C	18,143
Restrictions Because of:								
Darkness	NS	No	Yes ^F	No	No	Yes	Yes	Yes
Legal Holidays	NS	No	Yes ^F	Yes	No	Yes	Yes	Yes ^F
Weekends	NS	No	Yes ^F	No	No	No ^F	Yes	NS
Inclement Weather	NS	Yes	Yes ^F	Yes	Yes	Yes	Yes	Yes
Escort Vehicles Required:	NS	No ^F	Yes ^{I C}	Yes ^F	No	Yes ^F	Yes	Yes ^F

Footnotes:

- kg kilograms
- NS Not Specified
- A Manufacturers rating
- B Axle rating to 9,071 kg; tire size over 9,071 kg
- C Depends on axle spacings and route
- D Escort required if bridge restrictions of center line and 8 km per hour apply
- E 18,368 kg to 21,194 kg
- F There are exceptions
- G Except under special circumstances
- H Only if in combination with adjacent tandem or tridem with common suspension
- I If over lane width
- J Unless overweight only
- K 3.04 m wide x 30.48 m long allowed on Interstate highways at night
- L 3.65 m wide allowed on Interstate highways at night
- M Memorial Day and Labor Day
- N 4.26 m wide x 4.87 m high x 33.52 m long

NV	NM	ND	OK	OR	SD	TX	UT	WA	WY	WASHTO
272	272	272		272	272	294	^A	272		272
10,886	11,793	10,866	9,071	9,752 ^C	14,061	11,339	13,380	9,979	11,339	10,886
^E	23,586	20,411	18,143	19,504 ^C	23,586	23,586	22,679	19,504	24,947	20,411
No	Yes	Yes ^J	Yes	Yes ^L	No	Yes ^{KJ}	Yes	Yes ^F	No	No
No	Yes	Yes	Yes	Yes ^M	No	Yes ^N	Yes	Yes	No	No
No	Yes	Yes	No	Yes	No	No ^F	No	No	No	No
Yes	Yes	Yes	Yes	Yes ^M	Yes	Yes	Yes	Yes	No	No
No	Yes ^F	Yes ^F	No	No	No ^D	No ^F	Yes	Yes ^F	No ^D	No ^G

Transporting Manufactured Housing: National Network Appendix D and Other Designated Highways (U.S. Measurement)

	AK	AZ	CA	CO	HI	ID	MT	NE
Dimensions								
Width	A	A	16'	A	14'	16'	18'	16' ^A
Length (inc. tongue)	A	A	80'	A		80'		
Length (inc. tow vehicle)	A	A	105'	A	70'	110'		125'
Height	A	A	A	A	A	A	A	
Tow Vehicle								
Wheelbase	100"	99"		N/A	N/A		100"	120"
Gross Vehicle Weight	10,000	B	C			D	D	12,000
Axle Requirements	J	J				J	J	J
Movement Restrictions								
Night	Yes	^A	Yes ^A	Yes ^O	Yes	Yes	Yes	Yes
Weekend	Yes	^A	Yes ^A	Yes ^O	Yes	No	Yes	NS
Holiday	Yes	^A	Yes	Yes ^O		Yes	Yes	Yes
Inclement Weather	Yes		Yes			Yes	Yes	
Requirements								
Lights	Dot					Solid	Flash	
Lights	Beacon	Dot	Dot	Dot	Dot	Dot	Dot	
Signs	Yes	Yes	Yes	Yes	Yes	Yes	if>10'	if>10'
Pilot/Escort	if>10' ^X	Yes	Yes	Yes	if>12'	Yes	if>12'6"	Yes
Permits	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
Route Identification	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes

Footnotes:

- A Limited by route and/or time of day
 B 1.5 ton - 10 x 50; 2 ton - over 10 x 50
 C 6,500 lbs 8-12' wide; 9,500 lbs over 12'
 D 8,000 lbs 10-12' wide; 9,000 lbs over 12'
 E Plus 12" eave
 F ³/₄ ton less than 18,000#; 1¹/₂ ton over 18,000#
 G ³/₄ ton 10' or less wide; 2 ton over 10'
 H 89" cabover 120" conventional
 I 6,000 lbs less than 10'; 8,000 lbs 10-12'; 9,000 lbs over 12'
 J 4 tires on driving axle
 K Night travel on Interstate at 10' wide
 L 6,000 lbs less than 10' wide; 8,000 lbs 10-12'; 9,000 lbs over 12'
 M Yes if > 16' on Interstate or if > 20' on other highways
 N Dot and rotating if over 12' wide
 O Or limited by route
 P ¹/₂ hour before sunrise to ¹/₂ hour after sunset
 Q Restricted on the following holidays as well as the day before and the day after: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, and Christmas
 R Flashing or rotating beacon on top of tow vehicle, plus flashing or rotating beacon on roof at rear of manufactured home if escort vehicles not required
 S Signs meeting AASHTO guide required if manufactured home over 102" wide
 T Escorts required when over 12' wide on 2 lane highways and over 14' wide on multi-lane highways; Escorts must be at least 60" wide and no larger than 1³/₄ ton pickup
 U Plus 2' eaves
 V Discretion of permit authority
 W 16' base width allowed if hauled on licensed trailer
 X Or if overall length is greater than 85 feet
 Y 14' or > on 2 lane, 15' or > on divided
 Z 8,000 lbs up to 11'; 15,000 lbs up to 14'; 32,000 lbs over 14'

NV	NM	ND	OK	OR	SD	TX	UT	WA	WY	WASHTO
14'	16'	18'	16' ^O	14'	A	A	16'	16' ^{A EW}	A	14' ^U
	85'			75'	A					80'
85'	101'	120'		80'	A	A	A	75'		90'
A	A	A	A	A	A	A	A	A	A	14' ^O
	99">16'	100"		H			H	H		100"
F		L	G	Z	I		L	L		L
J		J		J			J	J		J
Yes	Yes	Yes	Yes	Yes ^K	Yes	Yes	Yes	Yes ^A	Daylight ^P	Daylight ^P
Yes	Yes	if>16'	No	Yes		No	No	No	No	
Yes	Yes	if>16'	Yes			Yes	Yes	Yes	Yes ^Y	Yes ^O
	Yes	Yes	Yes		Yes	Yes	Yes	Yes	Yes	
Flash	Flash	Flash	N	N				Flash		
Dot	Warning	Dot	Dot	Flash	None	N	Flash	Flash	Flash	R
Yes	A	Yes	Yes	Yes	Yes	No	if>10'	Yes	Yes	S
Yes	if>14'	if>16'	if>12'	if>12'	Yes ^{M V}	if>16'	if>12'	if>11'	Yes ^Y	T
Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes

Transporting Manufactured Housing: National Network Appendix D and Other Designated Highways (Metric Measurement)

	AK	AZ	CA	CO	HI	ID	MT	NE
Dimensions								
Width	A	A	4.87 m	A	4.26 m	4.87 m	5.48 m	4.87 m ^A
Length (inc. tongue)	A	A	24.38 m	A		24.38		
Length (inc. tow vehicle)	A	A	32.00 m	A	21.33 m			38.10 m
Height	A	A	A	A	A	A	A	

Tow Vehicle

Wheelbase	2,540 mm	2,514 mm		N/A	N/A		2.54 m	3.04 m
Gross Vehicle Weight	4,535 kg	B	C			D	L	
Axle Requirements	J	J				J	J	

Movement Restrictions

Night	Yes	A	Yes ^A	Yes ^O	Yes	Yes	Yes	Yes
Weekend	Yes	A	Yes ^A	Yes ^O	Yes	No	Yes	NS
Holiday	Yes	A	Yes	Yes ^O		Yes	Yes	Yes
Inclement Weather	Yes		Yes			Yes	Yes	

Requirements

Lights	Dot					Solid	Flash	
Lights	Beacon	Dot	Dot	Dot	Dot	Dot	Dot	
Signs	Yes	Yes	Yes	Yes	Yes	Yes	if>3.04m	if>3.04m
Pilot/Escort	if>3.04m ^X	Yes	Yes	Yes	if>3.65m	Yes	if>3.81m	Yes
Permits	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
Route Identification	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes

Footnotes:

m..... meter

mm millimeter

kg kilogram

A Limited by route and/or time of day

B 1,360 kg - 3.04 m x 15.24 m; 1,814 kg - over 3.04 m x 15.24 m

C 2,448 kg 2.43-3.65 m wide; 4,309 kg over 3.65 m

D 3,628 kg 3.04 m - 3.65 m wide; 4,309 kg over 3.65 m

E Plus .30 m eave

F 680 kg less than 8,164 kg; 1,360 kg over 8,164 kg

G 680 kg 3.04 m or less wide; 1,814 kg over 3.04 m

H 2,260 mm cabover 3,048 mm conventional

I 2,721 kg less than 3.04 m; 3,628 kg 3.04 m - 3.68 m; 4,082 kg over 3.65 m

J 4 tires on driving axle

K Night travel on Interstate at 3.04 m wide

L 2,271 kg less than 3.04 m wide; 3,628 kg 3.04 m - 3.68 m; 4,082 kg over 3.65 m

M Yes if > 4.87 m on Interstate or if > 6.09 m on other highways

N Dot and rotating if over 3.65 m wide

O Or limited by route

P 1/2 hour before sunrise to 1/2 hour after sunset

Q Restricted on the following holidays as well as the day before and the day after: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, and Christmas

R Flashing or rotating beacon on top of tow vehicle, plus flashing or rotating beacon on roof at rear of manufactured home if escort vehicles not required

S Signs meeting AASHTO guide required if manufactured home over 2,590 mm wide

T Escorts required when over 3.65 m wide on 2 lane highways and over 4.26 m wide on multi-lane highways; Escorts must be at least 1,524 mm wide and no larger than 1,587 kg pickup

U Plus .60 m eaves

V Discretion of permit authority

W 4.87 m base width allowed if hauled on licensed trailer

X Or if overall length is greater than 25.90 m

Y 4.26 m or > on 2 lane, 4.57 m or > on divided

Z 3,628 kg up to 3.35 m; 6,803 kg up to 4.26 m; 14,515 kg over 4.26 m

NV	NM	ND	OK	OR	SD	TX	UT	WA	WY	WASHTO
4.26 m	4.87 m	5.48 m	4.87 m	4.26 m	A	A	4.87 m	4.87 m ^{A EW}	A	4.26 m ^U
	29.50 m			22.86 m	A					24.38 m
29.50 m	30.78 m	36.57 m		24.38 m	A	A	A	22.86 m		27.43 m
A	A	A	A	A	A	A	A	A	A	4.26 m
	8.24 m > 4.87m	8.33 m		H			H	H		8.33 m
F		L	G	Z	I		L	L		L
J		J		J			J	J		J
Yes	Yes	Yes	Yes	Yes ^K	Yes	Yes	Yes	Yes	Daylight ^P	Daylight ^P
Yes	Yes	if > 4.87 m	No	Yes		No	No	No	No	
Yes	Yes	if > 4.87 m	Yes	Yes		Yes	Yes	Yes	Yes ^Y	Yes ^Q
		Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	
Flash	Flash	Flash	N	N			DOT	Flash		
Dot	Warning	Dot	Dot	Flash	None	N	Flash	Flash	Flash	R
Yes	A	Yes	Yes	Yes	Yes	No	if > 3.04m	Yes	Yes	S
Yes	if > 4.26m	if > 4.87m	if > 3.65m	if > 3.65m	Yes ^{M V}	if > 4.87m	if > 3.68m	if > 3.35m	Yes ^Y	T
Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes

Pilot/Escort Vehicles: National Network and Appendix E Other Designated Highways (U.S. Measurement)

Vehicle & Load Dimensions For Which Pilot/Escort Are Required	AK	AZ	CA	CO	HI	ID	MT	NE
Two Lane Highway								
Width	> 10'	12' ^I	> 10' ^A	13'	NS	12'1" ^C	12'7"	12' ^W
Length	> 85'	120'	^I	110' ^B	NS	100'	105'1"	100' ^W
Height	NS	16'		16'	NS	16'		16' ^W
Multi-Lane Highway								
Width	10'	14'	> 12'1" ^A	15'	NS	15'1"	16'7" ^S	12' ^W
Length	85'	120'	^I	115'	NS	120'	120'1"	100' ^W
Height	NS	16'		16'	NS	16'		16' ^W
Overhang								
Front	> 10' ^K		3' ^U		NS			
Rear	20' ^P	20'	^{2/3} wb	25'				
Holiday Restrictions	Yes	Yes ^J	Yes	Yes	NS	Yes ^J	Yes ^J	Yes
Manufactured Homes	Same	Same	Same	Same	NS	Same	Same	Same

Footnotes:

- NS..... Not Specified
A Or when vehicle/load exceed lane width
B 85' on two lane mountainous highways
C 10'1" on some mountainous highways
D Or second person in cab
E 12' in some situations
F Depends on load
G If over 16' on Interstate and over 20' on state system or discretion of permit authority
H 16' wide two pilot cars; 108' long two pilot cars
I Discretion of permit issuing authority
J Holiday travel allowed with reduced dimensions
K If truck crane, then overhang can be up to 18'
L 12' wide, required pilot car
M 14' one pilot car; two on all over 14'
N As required for restricted overweight move or whenever load extends to the left of centerline
O >16' one escort; > 18' two escorts
P >10'-20' may travel w/o escort if all req lighting is extended
Q New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving, and Christmas
R 12-14' one pilot car; 14-16' two pilot cars
S Unless highway is Interstate, the same requirements as two lane highways
T If escorts are required, shut down 1/2 hour after sunset, day before holiday or holiday weekend
 resume 1/2 hour before sunrise, day after holiday or holiday weekend
U Most vehicles limited to legal front overlong or 2/3 wheel base for cranes
V Front and rear pilot required; height pole required
W Requirement may be implemented at 8'6" wide, 14'6" high, or 90' long

NV	NM	ND	OK	OR	SD	TX	UT	WA	WY	WASHTO
12'	13'6"	if > 16'	14' ^E	^N	^G	> 14'	> 12'	11'	14'	^R
105' +	90' +	120'	80'	95'		> 110'	> 105'	100'	110'	105'
15'6"	16' ^D	18'	15'9" ^V	None		> 17'	> 16'	14'6"	^I	
14'	14' +	if > 16'	12' ^F	> 14'	16' ^G	> 14'	> 14'	14'	15'	14'
105' +	90' +	120'	80'	120'		> 110'	> 120'	140'	^I	120'
15'6"	16'	18'	15'9"	None		> 17'	16'	14'6"	^I	
25'				15' > (2 lane)		> 20'	> 20'	^I		
25'				None		> 20'	> 20'	1/3		20'
Yes ^J	^I	Yes ^J	Yes	Yes ^J	No	Yes ^{J Q}	Yes	Yes	Yes ^T	Yes ^Q
Same	Same	Same	^L	^M	Same	^O	Same	Same	Same	Same

Pilot/Escort Vehicles: National Network and Other Designated Highways (Metric Measurement)

Appendix E

Vehicle & Load Dimensions For Which Pilot/Escort Are Required	AK	AZ	CA	CO	HI	ID	MT	NE
Two Lane Highway								
Width	> 3.04 m	3.65 m ^I	> 3.04 m ^A	3.96 m	NS	3.68 m ^C	3.05 m	3.65 m ^W
Length	> 25.90 m	36.57 m	^I	33.52 m ^B	NS	30.48 m	32.02 m	30.48 m ^W
Height	NS	4.87 m		4.87 m	NS	4.87 m		4.87 m ^W
Multi-Lane Highway								
Width	> 3.04 m	4.26 m	> 3.68 m ^A	4.57 m	NS	4.59 m	5.05 m ^S	3.65 m ^W
Length	> 25.80 m	36.57 m	^I	35.02 m	NS	36.57 m	36.60 m	30.48 m ^W
Height	NS	4.87 m		4.87 m	NS	4.87 m		4.87 m ^W
Overhang								
Front	> 3.04 m ^K		.91 m ^U					
Rear	6.09 m ^P	6.09 m	^{2/3} wb	7.62 m				
Holiday Restrictions	Yes	Yes ^J	Yes	Yes	NS	Yes ^J	Yes ^J	Yes
Manufactured Homes	Same	Same	Same	Same	NS	Same	Same	Same

Footnotes:

- m..... meter
kg kilograms
NS..... Not Specified
A Or when vehicle/load exceed lane width
B 25.90 m on two lane mountainous highways
C 3.07 m on some mountainous highways
D Or second person in cab
E 3.65 m in some situations
F Depends on load
G If over 4.87 m on Interstate and over 6.09 m on state system or discretion of permit authority
I Discretion of permit issuing authority
J Holiday travel allowed with reduced dimensions
K If truck crane, then overhang can be up to 5.48 m
L 3.65 m wide, required pilot car
M 4.26 m one pilot car; two on all over 4.26 m
N As required for restricted overweight move or whenever load extends to the left of centerline
O >4.87 m one escort; > 5.48 m two escorts
P >3.04 m-6.09 m may travel w/o escort if all req lighting is extended
Q New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving, and Christmas
R 3.65 m-4.26 m one pilot car; 4.26 m-4.87 m two pilot cars
S Unless highway is Interstate, the same requirements as two lane highways
T If escorts are required, shut down 1/2 hour after sunset, day before holiday or holiday weekend
resume 1/2 hour before sunrise, day after holiday or holiday weekend
U Most vehicles limited to legal front overlong or 2/3 wheel base for cranes
V Front and rear pilot required; height pole required

NV	NM	ND	OK	OR	SD	TX	UT	WA	WY	WASHTO
3.65 m	4.11 m	> 4.87 m	4.26 m ^E	^N	^G	> 4.26 m	> 3.65 m	3.35 m	4.26 m	^R
32.00 m	27.43 m	36.57 m	24.38 m	24.95 m		> 33.52 m	> 32.00 m	30.48 m	33.52 m	32.00 m
4.72 m	4.87 m ^D	5.48 m	5.80 m	None		> 5.18 m	4.90 m	4.41 m	^I	
4.26 m	4.26 m+	> 4.87 m	3.65 m ^F	4.26 m	4.87 m ^G	> 4.26 m	> 4.26 m	4.26 m	4.57 m	4.26 m
32.00 m +	20.43 m+	36.57 m	24.38 m	36.57 m		> 33.52 m	> 36.57 m	42.67 m	^I	36.57 m
4.72 m	4.87 m	5.48 m	5.80 m	None		> 5.18 m	4.87 m	4.41 m	^I	
7.62 m				4.57 m (2 lane)		6.09 m	> 6.09 m	^I		
7.62 m				None		6.09 m	> 6.09 m	1/3		6.09 m
Yes ^J	^I	Yes ^J	Yes	Yes ^J	No	Yes ^{J Q}	Yes	Yes	Yes ^T	Yes ^Q
Same	Same	Same	^L	m	Same	^O	^P	Same	Same	Same

Appendix F Longer Combination Vehicles (U.S. Measurement)

	AK	AZ	CO	ID	MT	NE	NV	ND
Rocky Mountain Doubles								
Overall Length	120'	105'	NS	115'	95' ^D		NS	110'
Combined Trailer Length	95'	NS	NS	A	^D	65'	NS	NS
Semitrailer	53'	48'	48'	A	NS	53'	48'	53'
Trailer	48'	NS	28'6"	A	NS	53'	42'	53'
Turnpike Doubles								
Overall Length	120'	105' ^I	NS	115'	100'	N/A	NS	110'
Combined Trailer Length	95'	NS	NS	A	NS	N/A	NS	NS
Semitrailer	48'	NS	48'	A	NS	N/A	48'	53'
Trailer	48'	NS	48'	A	NS	N/A	42'	53'
Triple Trailer								
Overall Length	120' ^J	105'	NS	115'	NS	N/A	NS	110'
Combined Trailer Length	NS	NS	NS	A	95'	N/A	NS	NS
Individual Trailers	28'6"	NS	28'6"	A	28'6"	N/A	28'6"	53'
Maximum Gross Weight								
Uncapped		^I	110	105.5	Uncapped		129	80 ^K
(In 1000's lbs)	BFB	129			BFB	95		105.5
Bridge Formula Exceptions								
None	None	36	None	None	None	None	None	9 Axles
(In 1000's lbs)		Tandem						
		Min. 6 Axles						Maximum
		Max. 9 Axles						

Footnotes:

NS..... Not Specified

N/A ... Not Allowed

IN Interstate

NIN Non-Interstate

m..... meter

kg..... kilogram

A Must meet off track rule max. off track for 165' radius curve 6.5' on non-Interstate routes 8.75' on Interstate routes

B 95' for gas & LP transporters

C Conv. 110'

D 81' combined trailer length; if operating under 81' combined trailer length, 95' is not applicable

E 90,000 with permit on Interstate and approved non-Interstate routes

F Uncapped Formula B for rocky mountain doubles

G Interstate and 4-lane primary highways

H Must not exceed 8.75 off track for 161' radius curve (inside front tire)

I Specified by route

J Only allowed during the summer and on one specific route

K By permit on Interstate over 80,000 lbs

L By permit on all state highways

OK	OR	SD	TX	UT	WA	WY	WASHTO
NS ^G		NS	N/A	NS	^L	NS	NS
110'		81'6"		81'NIN/95'IN	68' ^L	81'	81'
53'	40'	45'		48'	53'	48'	48'
53'		NS		48'	53'	40'	NS
NS ^G	N/A	110'	N/A	NS	N/A	N/A	110'
110'	N/A	NS		95' IN	N/A	N/A	95'
53'	N/A	48' ^H		45'	N/A	N/A	45'
53'	N/A	48' ^H		45'	N/A	N/A	45'
NS ^G	105'	110'	N/A	NS	N/A	N/A	NS
95'	NS	NS		95'	N/A	N/A	NS
29'	28'6"	28'6"		28'6"	N/A	N/A	28'6"
80 ^E	105	129 ^F	N/A	129	105.5	117	105.5 to
90				BFB			129
None	None	None	N/A	None	None	36	NS
					Tandem		

Appendix F Longer Combination Vehicles (Metric Measurement)

	AK	AZ	CO	ID	MT	NE	NV	ND
Rocky Mountain Doubles								
Overall Length	86.57 m	28.04 m	NS	35.00 m	28.95 m ^D		NS	33.52 m
Combined Trailer Length	28.95 m	NS	NS	^A	^D	19.81 m	NS	NS
Semitrailer	16.15 m	13.71 m	14.63 m	^A	NS	16.15 m	14.63 m	16.15 m
Trailer	14.63 m	8.83 m	8.68 m	^A	NS	16.15 m	12.80 m	16.15 m
Turnpike Doubles								
Overall Length	36.57 m	32.00 m ^I	NS	35.00 m	30.48 m	N/A	NS	33.52 m
Combined Trailer Length	28.95 m	NS	NS	^A	NS		NS	NS
Semitrailer	14.63 m	NS	14.63 m	^A	NS	N/A	14.63 m	16.15 m
Trailer	14.63 m	NS	14.63 m	^A	NS	N/A	12.80 m	16.15 m
Triple Trailer								
Overall Length	36.57 m ^J	32.00 m	NS	35.00 m	NS	N/A	NS	33.52 m
Combined Trailer Length	NS	NS	NS	^A	28.95 m	N/A	NS	NS
Individual Trailers	8.68 m	8.68 m	8.68 m	^A	8.68 m	N/A	8.68 m	16.15 m
Maximum Gross Weight (kg)								
Uncapped		^I	48,895	47,853	Uncapped		58,513	36,287
BFB		56,018			BFB	43,091		47,853
Bridge Formula Exceptions (kg)								
None	None	16,329	None	None	None	None	None	9 Axles
		Tandem						Maximum
		Min. 6 Axles						
		Max. 9 Axles						

Footnotes:

NS..... Not Specified

N/A ... Not Allowed

IN Interstate

NIN Non-Interstate

m..... meter

kg..... kilogram

A Must meet off track rule max. off track for 50.29 m radius curve 1.98 m on non-Interstate routes 2.66 m on Interstate routes

C Conv. 33.52 m

D 24.68 m combined trailer length; if operating under 24.68 m combined trailer length, 28.95 m is not applicable

E 40,823 kg with permit on Interstate and approved non-Interstate routes

F..... Uncapped Formula B for rocky mountain doubles

G Interstate and 4-lane primary highways

H Must not exceed 2.66 m off track for 49.07 m radius curve (inside front tire)

I Specified by route

J..... Only allowed during the summer and on one specific route

K By permit on Interstate over 36,287 kg

L By permit on all state highways

OK	OR	SD	TX	UT	WA	WY	WASHTO
NS ^G		NS	N/A	NS	NS	NS	NS
33.52 m		24.84 m		24.68 mNIN/	20.72 m ^L	24.68 m	24.68 m
			28.95 mIN				
16.15 m	12.19 m	13.71		14.63 m	16.15 m	14.63 m	14.63 m
16.15 m		NS		14.63 m	16.15 m	12.19 m	NS
NS ^G	N/A	33.52 m	N/A	NS	N/A	N/A	33.52 m
33.52 m	N/A	NS		28.95 m	N/A	N/A	28.95 m
16.15 m	N/A	14.63 m		13.71 m	N/A	N/A	13.71 m
16.15 m	N/A	14.63 m		13.71 m	N/A	N/A	13.71 m
NS ^G	32 m	33.52 m	N/A	NS	N/A	N/A	NS
28.95 m	NS	NS		28.95 m	N/A	N/A	NS
8.83 m	8.68 m	8.68 m		8.68 m	N/A	N/A	8.68 m
36,287 ^E	47,627	58,513 ^F	N/A	58,513	47,853	53,070	47,853 to
40,823				BFB			58,513
None	None	None	N/A	None	None	16,329	NS
						Tandem	

Appendix G

Additional Longer Combination Vehicles (U.S. Measurement)

	AK	AZ	CA	CO	HI	ID	MT	NE
Full Truck & Trailer								
Overall Length	^P	92'	N/A		65' ^L	A & B	95'	N/A
Truck Length	45'	NS	N/A			NS	NS	N/A
Trailer Length	53'	40'	N/A		N/A	NS	NS	N/A
Full Truck & Trailer & Trailer								
Overall Length	N/A	NS	N/A	N/A	N/A	B & C	NS	N/A
Combined Trailer Length		NS	N/A			NS	95'	N/A
Trailer 1 Length		NS	N/A			NS	28'6"	N/A
Trailer 2 Length		NS	N/A			NS	28'6"	N/A
Dromedary Tractor & Trailer								
Overall Length	85' ^N	92'	N/A		N/A	B & C	NS	N/A
Semitrailer Length	53'	NS	N/A	40'		NS	57'	N/A
Dromedary Tractor & Trailer & Trailer								
Overall Length	N/A	N/A	N/A	N/A	N/A	B & C	0	N/A
Combined Trailer Length						NS	0	N/A
Semitrailer Length						NS	NS	N/A
Trailer Length						NS	NS	N/A
Dromedary Tractor & Trailer & Trailer & Trailer								
Overall Length	N/A	N/A	N/A	N/A	N/A	N/A	NS	N/A
Combined Trailer Length							95'	N/A
Semitrailer Length							28'6"	N/A
Trailer Length							28'6"	N/A
Truck Tractor Pole Trailer & Pole Trailer								
Overall Length	120' ^N	92'	N/A	N/A	N/A	A,B,C	95'	N/A
Combined Trailer Length	90'	NS				NS	NS	N/A
Trailer Length	48'					NS	NS	N/A
Maximum Gross Weight								
(in 1000's pounds)	Uncapped	111,000	80,000	110,000	80,000	105,500	Uncapped	95,000
Bridge Formula Exceptions								
(in 1000's pounds)	None	None	None	^J	^Q	None	None	None

Footnotes:

NS..... Not Specified

N/A ... Not Allowed

A Maximum length 85' with up to a 3' off track

B Maximum length 90' with up to a 5.5' off track

C Maximum length 105' with an off track up to 6.5' on non-Interstate routes and up to 8.75' on Interstate routes

D In a truck tractor, semitrailer, trailer configuration, combined trailer length cannot exceed 81' including connecting mechanisms; semitrailer cannot exceed 48' and the trailer cannot exceed 40'; no overall length limitations apply to this combination

E 95' on designated highways

F 110' on the National Network only

G May only operate on the Interstate and four lane divided Fed-Aid primary system; LCV permit up to 90,000 lbs on Interstate

H May operate on Interstate and four lane highways tractor and three trailers four lane highways are limited to a 5-mile access

I 80,000 on interstate 90,000 off interstate

J Formula $L + 40 \times 800$ (L=Length) not to exceed 20,000 on single axle nor 36,000 on tandem axles

K Longer vehicle combinations may operate by permit

NV	NM	ND	OK	OR	SD	TX	UT	WA	WY	WASHTO
NS	N/A	75' ^{E F}	70'	75'	80' ^K	N/A	65' ^R	75'	85'	
NS		50'		40'					60'	
NS		53'	59'6"	53'	NS		53'	53'	60'	
105'	N/A	75' ^{E F}	N/A	105'	NS	N/A	95'	N/A	85'	
NS		N/A	NS	NS	80'			N/A	NS	
28'6"		53'	NS	^U	28.5'		NS	N/A	60'	
28'6"		53'	NS	^U	28.5'		NS	N/A	60'	
NS	N/A	75' ^{E F}	NS	75'	NS	N/A	77' ^R	NS	85'	
		53'	59'6"	53'	53' ^K			53'	60'	
NS	N/A	75' ^{E F}	NS	^V	NS	N/A	N/A	NS	85'	
NS		N/A	110' ^G	68'	81.5' ^K		N/A	68' ^S	NS	
NS		53'	53'	40'	45'		53'	53'	60'	
NS		53'	53'	40'	45'		53'	53'	60'	
NS	N/A	75' ^{E F}	NS	N/A	N/A	N/A	N/A	N/A	N/A	
NS		N/A	95' ^H	N/A	N/A		N/A	N/A	N/A	
NS		53'	29'	N/A	N/A		N/A	N/A	N/A	
NS		53'	29'	N/A	N/A		N/A	N/A	N/A	
NS	N/A	75'	N/A	NS	NS	N/A	92'	N/A	N/A	
NS		N/A	N/A	68'	81.5' ^K			68'	81' ^D	
NS		53'	N/A	N/A	45'			N/A	^D	
80,000		105,000	^I	80,000 ^W	Uncapped		129,000	105,500	117,000	
None		None	None	Modified	None		None	None	36,000 ^T	

L No limit on allowable length on FAP highways

M Triples operation, Interstate only; combined trailer length is measured from the front of the cargo carrying unit on the truck to the rearmost portion of the second trailer, including connection tongues and load

N Special designated routes

O 95' combination length or 81' combined trailer length, provided the longer trailer does not exceed 48'

P Special designated routes 90' overall without permit, other designated routes 85'

Q 88,000 other than Interstate – Exception
W=900 (L+40)

R May go up to 85' overall with off track approval

S By permit on all state highways

T Per tandem

U Truck length limit 35'; no more than 40' trailer; no variation more than 8'

V Variable based on highway

W By permit to 105,500 lbs

Appendix G

Additional Longer Combination Vehicles (Metric Measurement)

	AK	AZ	CA	CO	HI	ID	MT	NE
Full Truck & Trailer								
Overall Length	^P	28.04 m	N/A		19.81 m ^L	A & B	28.95 m	N/A
Truck Length	13.71 m	NS	N/A			NS	NS	N/A
Trailer Length	16.15 m	12.19 m	N/A		N/A	NS	NS	N/A

Full Truck & Trailer & Trailer								
Overall Length	N/A	NS	N/A	N/A	N/A	B & C	NS	N/A
Combined Trailer Length		NS	N/A			NS	28.95 m	N/A
Trailer 1 Length		NS	N/A			NS	8.68 m	N/A
Trailer 2 Length		NS	N/A			NS	8.68 m	N/A

Dromedary Tractor & Trailer								
Overall Length	25.90 m ^N	28.04 m	N/A		N/A	B & C	NS	N/A
Semitrailer Length	16.15 m	NS	N/A	12.19 m		NS	17.37 m	N/A

Dromedary Tractor & Trailer & Trailer								
Overall Length	N/A	N/A	N/A	N/A	N/A	B & C	0	N/A
Combined Trailer Length						NS	0	N/A
Semitrailer Length						NS	NS	N/A
Trailer Length						NS	NS	N/A

Dromedary Tractor & Trailer & Trailer & Trailer								
Overall Length	N/A	N/A	N/A	N/A	N/A	N/A	NS	N/A
Combined Trailer Length							28.95 m	N/A
Semitrailer Length							8.68 m	N/A
Trailer Length							8.68 m	N/A

Truck Tractor Pole Trailer & Pole Trailer								
Overall Length	36.59 m ^N	28.04 m	N/A	N/A	N/A	A B C	28.95 m	N/A
Combined Trailer Length	27.45 m	NS				NS	NS	N/A
Trailer Length	14.63 m					NS	NS	N/A

Maximum Gross Weight								
(kg)	Uncapped	50,348	36,287	49,895	36,287	47,583	Uncapped	43,091

Bridge Formula Exceptions								
(kg)	None	None	None	^J	^Q	None	None	None

Footnotes:

NS..... Not Specified

N/A ... Not Allowed

kg kilogram

m meter

A Maximum length 25.90 m with up to a .91 m off track

B Maximum length 25.90 m with up to a 1.67 m off track

C Maximum length 32.00 m with an off track up to 1.98 m on non-Interstate routes and up to 2.66 m on Interstate routes

D In a truck tractor, semitrailer, trailer configuration, combined trailer length cannot exceed 24.68 m including connecting mechanisms; semitrailer cannot exceed 14.63 m and the trailer cannot exceed 12.19 m; no overall length limitations apply to this combination

E 28.95 m on designated highways

F 33.52 m on the National Network only

G May only operate on the Interstate and four lane divided Fed-Aid primary system; LCV permit up to 40,823 kg on Interstate

H May operate on Interstate and four lane highways tractor and three trailers four lane highways are limited to a 8.04 km access

I 36,287 kg on interstate 40,823 kg off Interstate

J Formula $L + 12.19 \text{ m} \times 800$ (L=Length) not to exceed 9,071 kg on single axle nor 16,329 kg on tandem axles

K Longer vehicle combinations may operate by permit

L No limit on allowable length on FAP highways

NV	NM	ND	OK	OR	SD	TX	UT	WA	WY	WASHTO
NS	N/A	22.86 m ^{E F}	21.33 m	31.68 m	24.38 m ^K	N/A	19.81 m ^R	22.86 m	25.90 m	
NS		15.24 m		12.19 m				12.19 m	18.28 m	
NS		16.15 m	18.13 m	16.15 m	NS		16.15 m	16.15 m	18.28 m	
32.00 m	N/A	22.86 m ^{E F}	N/A	32.00 m	NS	N/A	28.95 m	N/A	25.90 m	
NS		N/A	NS	NS	24.38 m			N/A	NS	
8.68 m		16.15 m	NS	^U	8.68 m		NS	N/A	18.28 m	
8.68 m		16.15 m	NS	^U	8.68 m		NS	N/A	18.28 m	
NS	N/A	22.86 m ^{E F}	NS	31.68 m	NS	N/A	23.46 m ^R	NS	55.90 m	
		16.15 m	18.16 m	16.15 m	16.15 m ^K			16.15 m	18.28 m	
NS	N/A	22.86 m ^{E & F}	NS	^V	NS	N/A	N/A	NS	25.90 m	
NS		N/A	33.52 m ^G	20.78 m	24.84 m ^K		N/A	20.72 m ^S	NS	
NS		16.15 m	16.15 m	12.19 m	13.71 m		16.15 m	16.15 m	18.28 m	
NS		16.15 m	16.15 m	12.19 m	13.71 m		16.15 m	18.28 m	18.28 m	
NS	N/A	22.86 m ^{E & F}	NS	N/A	N/A	N/A	N/A	N/A	N/A	
NS		N/A	28.95 m ^H	N/A	N/A		N/A	N/A	N/A	
NS		16.15 m	8.83 m	N/A	N/A		N/A	N/A	N/A	
NS		16.15 m	8.83 m	N/A	N/A		N/A	N/A	N/A	
NS	N/A	22.86 m	N/A	NS	NS	N/A	28.04 m	N/A	N/A	
NS		N/A	N/A	20.78 m	24.84 m ^K			20.72 m	24.68 m ^D	
NS		53'	N/A	N/A	13.71 m			N/A	^D	
47,583		47,853	^I	36,287 ^W	Uncapped		58,513	47,583	53,070	
None		None	None	Modified	None		None	None	16,329 ^T	

M Triples operation, Interstate only; combined trailer length is measured from the front of the cargo carrying unit on the truck to the rearmost portion of the second trailer, including connection tongues and load

N Special designated routes

O 28.95 m combination length or 24.68 m combined trailer length, provided the longer trailer does not exceed 14.63 m

P Special designated routes 27.43 m overall without permit, other designated routes 25.90 m

Q 39,916 kg other than Interstate – Exception W=900 (L+12.19 m)

R May go up to 25.90 m overall with off track approval

S By permit on all state highways

T Per tandem

U Truck length limited to 10.66 m; no more than 12.19 m trailer; no variation greater than 2.43 m

V Variable base on highway

W By permit to 47,854 kg

Appendix H

Canadian Vehicle Weight Limits

Gross Vehicle Weights	Yukon Territories		British Columbia		Alberta	
	Kg	Lbs	Kg	Lbs	Kg	Lbs
Truck 3 - Axles	26,900	59,304	26,100	57,540	24,300	53,572
Truck - Tandem/Tandem	34,900	76,941	34,000	74,957	30,600	67,461
Truck & Pony - 6 Axles	55,500	122,356	47,100	103,837	45,300	99,869
Truck & Full - 5 Axles	43,700	96,342	44,300	97,664	42,500	93,696
Truck & Full - 7 Axles	63,300	139,552	57,100	125,883	55,300	121,660
Tractor Semitrailer - 3 Axles			24,200	53,351		
- 4 Axles			31,600	72,311		
- 5 Axles	44,000	97,003	39,500	87,081	39,500	87,081
- 6 Axles	54,000	119,049	46,500	102,513	46,500	102,513
A Train- 5 Axles			38,000	83,775	41,900	92,373
- 6 Axles			50,300	110,892	49,800	109,789
- 7 Axles	63,500	139,993	53,500	117,947	53,500	117,947
- 8 Axles	63,500	139,993	53,500	117,947	53,500	117,947
Second Trailer Weight	NR					
B Train - 5 Axles			38,000	83,775		
- 6 Axles			48,600	107,144		
- 7 Axles	63,500	139,993	56,500	124,561	56,500	124,561
- 8 Axles	63,500	139,993	63,500	139,993	63,500	139,993
C Train* - 5 Axles			38,000	83,774		
- 6 Axles			49,800	109,789		
- 7 Axles	63,500	139,993	57,700	127,206	57,700	127,206
- 8 Axles	63,500	139,993	60,500	133,378	60,500	133,379
Second Trailer Weight	NR					
Axle Loads						
Steering Axle (Truck-Tractor)	9,000	19,841	9,100	20,062	5,500	12,125
Single Axle Dual Tires	10,000	2,204	9,100	20,062	9,100	20,062
Tandem - 1.2 M Spread	16,800	37,037	17,000	37,478	17,000	37,478
Tandem - 1.8 M Spread	19,100	42,108	17,000	37,478	17,000	37,478
Tridem - 2.4 To 3.0 M Spread	22,400	46,958	24,000	52,910	21,000	46,279
Tridem - 3.0 To 3.6 M Spread	24,100	52,910	24,000	52,910	24,000	52,910
Tridem - 3.7 M Spread	24,400		24,000	52,910	24,000	52,910
Triaxle - 1.5 M + 2.5 M	27,900	61,508	NP		17,000	37,478
Triaxle - 1.8 M + 3.0 M	29,100	64,154	NP		17,000	37,478

*C Train Applicable Only to Combinations with CMVSS Approved C Dolly Converters.

Footnotes:

Blank Same As MOU

SP Special Permit Required

NR Not Regulated

NP Not Permitted

Lbs Pounds

Kg Kilograms

Saskatchewan		Manitoba		NW Territories		MOU	
Kg	Lbs	Kg	Lbs	Kg	Lbs	Kg	Lbs
		24,300	53,572			22,500	49,604
28,000	61,729	SP		39,500	87,081	NP	
		45,300	99,869	46,500	102,513	43,500	95,901
40,700	89,728	41,300	91,050			39,500	87,082
		55,300	121,915			53,500	117,947
				23,700		52,249	
						31,600	69,666
						39,500	87,082
						46,500	102,514
41,900	92,373	41,900	92,373			39,700	87,523
48,800	109,789	48,800	107,584			47,600	104,940
		55,500	122,356			53,500	117,947
		55,500	122,356			53,500	117,947
NR						16,000	35,273
						40,700	89,728
						48,600	107,144
						56,500	124,561
						62,500	137,788
				41,900		92,373	
						49,800	109,790
53,500	117,947	60,500	133,379	57,700	127,205	54,600	120,372
		60,500	133,379			58,500	128,970
NR						21,000	46,297
						5,500	12,125
						9,100	20,062
						17,000	37,478
						17,000	37,478
						21,000	46,297
						23,000	50,706
						24,000	52,910
NP		NP		NR		NP	
NP		NP		NR		NP	

Appendix I

Canadian Dimension Limits

	Yukon Territories		British Columbia		Alberta		Saskatchewan	
	M	FT	M	FT	M	FT	M	FT
Overall Height (Max)	4.20	13.77	4.15	13.61	4.15	13.61		4.15
Overall Width (Max)	2.60	8.50	2.60	8.50	2.60	8.50		
Overall Length (Max)			25.00	82.02				

Straight Truck

Truck & Full Trailer	22.00	72.17	23.00	75.45	23.00	75.45		
Truck & Pony Trailer			23.00	75.45	23.00	75.45		
Tractor Semitrailer	23.00	72.17	23.00	75.45	23.00	75.45		
A Train	25.00	82.02	25.00	82.02	25.00	82.02	25.00	82.02
B Train	25.00	82.02	25.00	82.02	25.00	82.02	25.00	82.02
C Train	25.00	82.02	25.00	82.02	25.00	82.02	25.00	82.02

Trailer Length (Max)

Full Trailer	16.20	44.29	12.50	41.01	12.50	41.01	16.20	53.14
Semitrailer	16.20	44.29	16.20	53.14	16.20	53.14	16.20	53.14

Box Length (Max)

Truck & Full Or Pony Trailer	NR		20.00	65.61	20.00	65.61		
A Train	NR		20.00	65.61	20.00	65.61		
B Train	NR		20.00	65.61	20.00	65.61		
C Train	NR		20.00	65.61	20.00	65.61		

Effective Rear Overhang

Straight Truck (Max)			4.00	13.12	4.00	13.12	NR	
Semitrailer (Max)			35% of WB		35% of WB			
Full Trailer (Max)			35% of WB				4.10	
Pony Trailer (Max)			4.00	13.12	4.00	13.12	4.10	

Wheelbase

Tractor (Max)	NR		6.20	20.34	6.20	20.34		
Full Trailer (Min)	NR		6.25	20.50	6.25	20.50		
Semitrailer (Max)	NR		12.50	41.01	12.50	41.01		
Semitrailer (Min)	NR		6.25	20.50	6.25	20.50		
Semitrailer With Tridem (Min)	NR		6.25	20.50	6.25	20.50	6.50	21.32

Footnotes:

NA Not Available

Blank ... Same As MOU (*what is MOU?*)

MOU Memorandum of Understanding between Provinces

SP Special Permit Required

NR Not Regulated

NP Not Permitted

M Meters

FT Feet

WB Wheelbase

Manitoba		NW Territories		MOU	
M	FT	M	FT	M	FT
	4.20		4.15	13.61	
2.60	8.50	2.60	8.50	2.60	8.50
25.00	82.02	26.00	85.30		
				12.50	41.01
		21.00		23.00	75.45
		21.00	75.45	23.00	75.45
		25.00		23.00	75.45
25.00	82.02	25.00		23.00	75.45
25.00	82.02	25.00		23.00	75.45
25.00	82.02	25.00		23.00	75.45
		NR		12.50	41.01
16.20	53.14	NR		16.20	53.14
		NR		20.00	65.62
20.00	65.62	NR		18.50	60.69
20.00	65.62	NR		20.00	65.62
20.00	65.62	NR		20.00	65.62
4.00		NR		4.00	13.12
				35% of WB	
NR		35% of WB	35% of WB	NR	
		35% of WB	35% of WB	4.00	13.12
				6.20	20.34
6.25	20.50	5.00	16.40	6.50	21.32
		NR		12.50	41.01
6.25	20.50	5.00	16.40	6.50	21.32
6.25	20.50	5.50	18.04	9.50	31.16

Appendix J







Mexican Vehicle Weight Limits

Configuration De Ejes Vehicle Configurations







			A4 Y A2 Metric Tons	Pounds
I—I 0	Sencillo Dos Llantas	Single Axle Single Tires	6.50	14,330
I—I 0	Motriz Sencillo Dos Llantas	Drive Axle Single Tires	7.00	15,432
II—II 0	Sencillo Cuatro Llantas	Single Axle Dual Tires	10.00	22,046
II—II 0	Motriz Sencillo Cuatro Llantas	Drive Axle Dual Tires	11.00	24,250
I—I 00 I—I	Doble 0 Tandem Cuatro Llantas	Dual Axle Single Tires	11.00	24,250
I—I 00 I—I	Motriz Doble 0 Tandem Cuatro Llantas	Dual Drive Axle Single Tires	12.50	27,557
II—II 00 I—I	Doble 0 Tandem Seis Llantas	Dual Axle 6 Tires	14.50	31,967
II—II 00 I—I	Motriz Doble 0 Tandem Seis Llantas	Dual Drive 6 Tires	15.50	34,171
II—II 00 II—II	Doble 0 Tandem Ocho Llantas	Dual Axle Dual Tires	18.00	39,683
II—II 00 II—II	Motriz Doble 0 Tandem Ocho Llantas	Dual Drive Axle Dual Tires	19.50	42,990
I—I 000 I—I I—I	Triple 0 Tridem Seis Llantas	Triple Axle Single Tires	14.00	30,864
I—I 000 I—I I—I	Motriz Triple 0 Tridem Seis Llantas	Triple Drive Axle Single Tires	15.50	34,171
II—II 000 II—II II—II	Triple 0 Tridem Doce Llantas	Triple Axle Dual Tires	22.50	49,604
II—II 000 II—II II—II	Motriz Triple 0 Tridem Doce Llantas	Triple Drive Axle Dual Tires	24.50	54,013

Tipo De Camino B4 Y B2 Metric Tons	Pounds	Road Type C Metric Tons	Pounds	D Metric Tons	Pounds
6.50	14,330	5.50	12,125	5.00	11,023
7.00	15,432	6.00	13,227	5.50	12,125
10.00	22,046	9.00	19,841	8.00	17,636
11.00	24,250	10.00	22,046	9.00	19,841
11.00	24,250	10.00	22,046	9.00	19,841
12.50	27,557	11.00	24,250	10.00	22,046
14.50	31,967	13.00	28,660	11.50	25,353
15.50	34,171	14.00	30,864	12.50	27,557
18.00	39,683	16.00	35,273	14.00	30,864
19.50	42,990	17.50	38,580	15.50	34,171
14.00	30,864	12.50	41,017	11.50	37,723
15.50	34,171	14.00	30,864	12.50	27,557
22.50	49,604	20.00	44,092	18.00	39,683
24.50	54,010	22.00	48,501	19.50	42,990

Camion / Full Truck

Configuracion Del Vehiculo Vehicle Configurations	Numero De Llantas	Number of Tires	A4 Y A2		B4 Y B2	
			Metric Tons	Pounds	Metric Tons	Pounds
C2 (4/6) 	Cuatro Llantas	4	13.50	29,762	13.50	29,762
	Seis Llantas	6	17.50	38,580	17.50	38,580
C3 (6/10) 	Seis Llantas	6	19.00	41,887	19.00	41,887
	Diez Llantas	10	26.00	57,320	26.00	57,320
C4 (8/14) 	Ocho Llantas	8	22.00	48,501	22.00	48,501
	Catorce Llantas	14	31.00	68,343	31.00	68,343

Camion Remolque / Full Truck and Trailer

Configuracion Del Vehiculo Vehicle Configurations	Numero De Llantas	Number of Tires	A4 Y A2		B4 Y B2	
			Metric Tons	Pounds	Metric Tons	Pounds
C2-R2 (8/14) 	Ocho Llantas	8	26.50	58,422	26.50	58,422
	Catorce Llantas	14	37.50	82,673	37.50	82,673
C3-R2 (10/18) 	Diez Llantas	10	32.00	70,547	32.00	70,547
	Dieciocho Llantas	18	46.00	101,412	46.00	101,412
C3-R3 (12/22) 	Doce Llantas	12	36.50	80,468	36.50	80,468
	Vientidos Llantas	22	54.00	119,049	54.00	119,049

Footnotes:

El Peso Bruto Vehicular (Pbv) Maximo Autorizado Podra Incrementarse Hasta Un Cinco Porciento (5%), Si El Vehiculo Esta Equipado Con Suspension Neumatic O Equivalente En Todos Sus Ejes, Excepto En El Eje Direccional.





Road Type			
C		D	
Metric Tons	Pounds	Metric Tons	Pounds
11.50	25,353	11.00	24,250
15.50	34,171	14.00	30,864
16.50	36,376	15.00	33,069
23.00	50,706	20.50	45,194
19.50	42,990	17.50	38,580
27.50	60,627	24.50	54,013

Road Type		
C		D
Metric Tons	Pounds	
22.50	49,604	N/A
33.50	73,854	N/A
27.50	60,627	N/A
41.00	90,389	N/A
32.00	70,547	N/A
48.00	105,821	N/A

The gross vehicle weight authorized can be increased 5% if the vehicle is equipped with pneumatic suspension or equivalent on all its axles except the steer axle.

Tractocamion Articulado / Truck Tractor and Trailer

Configuración Del Vehículo Vehicle Configurations

	Numero De Llantas	Number of Tires	Tipo De Camino / Road Type	
			A4 Y A2 Metric Tons	Pounds
T2-S1 (8/10) 	OCHO LLANTAS	8	24.00	52,910
	DIEZ LLANTAS	10	27.50	60,627
T2-S2 (10/14) 	DIEZ LLANTAS	10	28.50	62,831
	CATORCE LLANTAS	14	35.50	78,264
T3-S2 (18) 	DIECIOCHO LLANTAS	18	44.00	97,003
T3-S3 (16/22) 	DIECISEIS LLANTAS	16	40.00	88,184
	VEINTIDOS LLANTAS	22	48.50	88,184

Footnotes:





El peso bruto vehicular (pbv) máximo autorizado podrá incrementarse hasta un cinco por ciento (5%), si el vehículo está equipado con suspensión neumática o equivalente en todos sus ejes, excepto en el eje direccional.

The gross vehicle weight authorized can be increased 5% if the vehicle is equipped with pneumatic suspension or equivalent on all its axles except the steer axle.

Tipo De Camino / Road Type					
B4 Y B2		C		D	
Metric Tons	Pounds	Metric Tons	Pounds	Metric Tons	Pounds
24.00	52,910	21.00	46,297	N/A	
27.50	60,627	24.50	54,013	N/A	
28.50	62,831	25.50	56,217	N/A	
35.50	78,264	31.50	69,445	N/A	
44.00	97,003	39.00	85,980	N/A	
40.00	88,184	35.50	78,264	N/A	
48.50	106,924	43.00	94,798	N/A	

Tractocamion Doblemente Articulado / Truck Tractor and Trailer and Trailer

Configuración Del Vehículo Vehicle Configurations

	Numero De Llantas	Number of Tires	Tipo De Camino / Road Type	
			A4 Y A2 Metric Tons	Pounds
T2-S1-R2 (12/18)	DOCE LLANTAS	12	37.00	81,571
	DIECIOCHO LLANTAS	18	47.50	104,719
T3-S1-R2 (16/22)	DIECISEIS LLANTAS	16	45.50	100,310
	VEINTIDOS LLANTAS	22	56.00	123,458
T3-S2-R2 (18/26)	DICIOCHO LLANTAS	18	50.00	110,231
	VEINTISEIS LLANTAS	26	60.50	133,379
T3-S2-R4 (22/34)	VEINTIDOS LLANTAS	22	59.00	130,072
	TREINTA Y CUATRO LLANTAS	34	66.5*	146,607

Footnotes:

El peso bruto vehicular (pbv) maximo autorizado podra incrementarse hasta un cinco porciento (5%), si el vehiculo esta equipado con suspension neumatica o equivalente en todos sus ejes, excepto en el eje direccional.





The gross vehicle weight authorized can be increased 5% if the vehicle is equipped with pneumatic suspension or equivalent on all its axles except the steer axle.

* el peso bruto vehicular para este tipo de unidades que trasladan gases o quimicos por caminos tipo "a" sera de 72.5 ton. Por un periodo de 5 años a partir de la expedición del presente reglamento, posteriormente a este periodo deberán ajustarse al valor endicado.

The unit's gross vehicle weight, that transports gases and chemicals, over road type a would be 72.5 ton. For a period of 5 years as of this rule, before this rule you should adjust the weights indicated.

Tipo De Camino / Road Type					
B4 Y B2		C		D	
Metric Tons	Pounds	Metric Tons	Pounds	Metric Tons	Pounds
37.00	81,571	32.00	70,547	N/A	
47.50	104,719	42.50	93,696	N/A	
45.50	100,310	39.50	87,082	N/A	
55.00	121,254	50.00	110,231	N/A	
50.00	110,231	44.00	97,003	N/A	
58.00	127,868	52.50	115,742	N/A	
59.00	130,072	53.00	116,845	N/A	
64.00	141,095	58.00	127,868	N/A	

Tractocamion Articulado / Truck Tractor and Trailer

Configuración Del Vehículo Vehicle Configurations	Tipo De Vehículo	Type of Vehicle	Tipo De Camino / Road Type	
			A4 Y A2 M	FT
T2-S1 (8/10) 	Tracto Camion Semir Remolque	Truck Tractor & Trailer	A = 2.50 L = 19.50	W = 8.20 L = 63.97
	Tres Ejes	3 Axles	A = 2.60 L = 19.00	W = 8.53 L = 62.33
T2-S2 (10/14) 	Tracto Camion Semir Remolque	Truck Tractor & Trailer	A = 2.50 L = 19.50	W = 8.20 L = 63.97
	Cuatro Ejes	4 Axles	A = 2.60 L = 19.00	W = 8.53 L = 62.33
T3-S2 (18) 	Tracto Camion Semir Remolque	Truck Tractor & Trailer	A = 2.50 L = 19.50	W = 8.20 L = 63.97
	Cinco Ejes	5 Axles	A = 2.60 L = 19.00	W = 8.53 L = 62.33
T3-S3 (16-22) 	Tracto Camion Semir Remolque	Truck Tractor & Trailer	A = 2.50 L = 19.50	W = 8.20 L = 63.97
	Cinco Ejes	6 Axles	A = 2.60 L = 19.00	W = 8.53 L = 62.33

Footnotes:

A Ancho Del Vehículo

L Longitud Del Vehículo

H Altura Del Vehículo 4.15 M

W Width of Vehicle

L Length of Vehicle

H Height 13.61 Ft

Tipo De Camino / Road Type				
B4 Y B2 M	FT	C M	FT	D M
A = 2.50 L = 18.00	W = 8.20 L = 59.05	A = 2.50 L = 16.50	W = 8.20 L = 54.13	N/A
A = 2.60 L = 17.00	W = 8.53 L = 55.77	A = 2.60 L = 16.00	W = 8.53 L = 52.49	N/A
A = 2.50 L = 18.00	W = 8.20 L = 59.05	A = 2.50 L = 16.50	W = 8.20 L = 54.13	N/A
A = 2.60 L = 17.00	W = 8.53 L = 55.77	A = 2.60 L = 16.00	W = 8.53 L = 52.49	N/A
A = 2.50 L = 18.00	W = 8.20 L = 59.05	A = 2.50 L = 16.50	W = 8.20 L = 54.13	N/A
A = 2.60 L = 17.00	W = 8.53 L = 55.77	A = 2.60 L = 16.00	W = 8.53 L = 52.49	N/A
A = 2.50 L = 18.00	W = 8.20 L = 59.05	A = 2.50 L = 16.50	W = 8.20 L = 54.13	N/A
A = 2.60 L = 17.00	W = 8.53 L = 55.77	A = 2.60 L = 16.00	W = 8.53 L = 52.49	N/A

Tractocamion Doblemente Articulado / Truck Tractor and Trailer and Trailer

Configuración
Del Vehículo
Vehicle
Configurations

	Tipo De Vehículo	Type of Vehicle	Tipo De Camino / Road Type	
			A4 Y A2 M	FT
T2-S1-R2 (12/18) 	Tracto Camion Articulado Multiple	Truck Tractor Trailer & Trailer	A = 2.50 L = 28.50	W = 8.20 L = 93.50
	Cinco Ejes	5 Axles	A = 2.60 L = 27.50	W = 8.53 L = 90.22
T3-S1-R2 (16/22) 	Tracto Camion Articulado Multiple	Truck Tractor Trailer & Trailer	A = 2.50 L = 28.50	W = 8.20 L = 93.50
	Seis Ejes	6 Axles	A = 2.60 L = 27.50	W = 8.53 L = 90.22
T3-S2-R2 (18/26) 	Tracto Camion Articulado Multiple	Truck Tractor Trailer & Trailer	A = 2.50 L = 28.50	W = 8.20 L = 93.50
	Seite Ejes	7 Axles	A = 2.60 L = 27.50	W = 8.53 L = 90.22
T3-S2-R4 (22/34) 	Tracto Camion Articulado Multiple	Truck Tractor Trailer & Trailer	A = 2.50 L = 28.50	W = 8.20 L = 93.50
	Nueve Ejes	9 Axles	A = 2.60 L = 27.50	W = 8.53 L = 90.22

Footnotes:

A Ancho Del Vehículo

L Longitud Del Vehículo

H Altura Del Vehículo 4.15 M




W Width of Vehicle

L Length of Vehicle

H Height 13.61 Ft

Tipo De Camino / Road Type				
B4 Y B2 M	FT	C M	FT	D M
A = 2.50 L = 24.00	W = 8.20 L = 78.74	A = 2.50 L = 23.50	W = 8.20 L = 77.09	N/A
A = 2.60 L = 23.00	W = 8.53 L = 75.45	A = 2.60 L = 22.50	W = 8.53 L = 73.81	N/A
A = 2.50 L = 24.00	W = 8.20 L = 78.74	A = 2.50 L = 23.50	W = 8.20 L = 77.09	N/A
A = 2.60 L = 23.00	W = 8.53 L = 75.45	A = 2.60 L = 22.50	W = 8.53 L = 73.81	N/A
A = 2.50 L = 24.00	W = 8.20 L = 78.74	A = 2.50 L = 23.50	W = 8.20 L = 77.09	N/A
A = 2.60 L = 23.00	W = 8.53 L = 75.45	A = 2.60 L = 22.50	W = 8.53 L = 73.81	N/A
A = 2.50 L = 24.00	W = 8.20 L = 78.74	A = 2.50 L = 23.50	W = 8.20 L = 77.09	N/A
A = 2.60 L = 23.00	W = 8.53 L = 75.45	A = 2.60 L = 22.50	W = 8.53 L = 73.81	N/A

Camion / Full Truck

Configuración Del Vehículo Vehicle Configurations	Tipo De Vehículo	Type of Vehicle	Tipo De Camino / Road Type	
			A4 Y A2 M	FT
C2 (4/6) 	Camion	Full Truck	A = 2.50 L = 14.00	W = 8.20 L = 45.93
	Dos Ejes	2 Axles	A = 2.60 L = 13.71	W = 8.53 L = 44.98
C3 (6/10) 	Camion	Full Truck	A = 2.50 L = 14.00	W = 8.20 L = 45.93
	Tres Ejes	3 Axles	A = 2.60 L = 13.71	W = 8.53 L = 44.98
C4 (8/14) 	Camion	Full Truck	A = 2.50 L = 14.00	W = 8.20 L = 45.93
	Cuatro Ejes	4 Axles	A = 2.60 L = 13.71	W = 8.53 L = 44.98

Footnotes:

A Ancho Del Vehículo

L Longitud Del Vehículo

H Altura Del Vehículo 4.15 M




W Width of Vehicle

L Length of Vehicle

H Height 13.61 Ft

Tipo De Camino / Road Type					
B4 Y B2 M	FT	C M	FT	D M	FT
A = 2.50 L = 14.00	W = 8.20 L = 45.93	A = 2.50 L = 14.00	W = 8.20 L = 45.93	A = 2.50 L = 12.50	W = 8.20 L = 41.01
A = 2.60 L = 17.00	W = 8.53 L = 55.77	A = 2.60 L = 16.00	W = 8.53 L = 52.49	A = 2.60 L = 12.25	W = 8.53 L = 40.19
A = 2.50 L = 18.00	W = 8.20 L = 59.05	A = 2.50 L = 16.50	W = 8.20 L = 54.13	A = 2.50 L = 12.50	W = 8.20 L = 41.01
A = 2.60 L = 17.00	W = 8.53 L = 55.77	A = 2.60 L = 16.00	W = 8.53 L = 52.49	A = 2.60 L = 12.25	W = 8.53 L = 40.19
A = 2.50 L = 18.00	W = 8.20 L = 59.05	A = 2.50 L = 16.50	W = 8.20 L = 54.13	A = 2.50 L = 12.50	W = 8.20 L = 41.01
A = 2.60 L = 17.00	W = 8.53 L = 55.77	A = 2.60 L = 16.00	W = 8.53 L = 52.49	A = 2.60 L = 12.25	W = 8.53 L = 40.19

Camion Remolque / Full Truck and Trailer

Configuración Del Vehículo Vehicle Configurations	Tipo De Vehículo	Type of Vehicle	Tipo De Camino / Road Type	
			A4 Y A2 M	FT
C2-R2 (8/14) 	Camion Remolque	Full Truck	A = 2.50 L = 28.50	W = 8.20 L = 93.50
	Cuatro Ejes	4 Axles	A = 2.60 L = 27.00	W = 8.53 L = 88.58
C3-R2 (10/18) 	Camion Remolque	Full Truck	A = 2.50 L = 28.50	W = 8.20 L = 93.50
	Cinco Ejes	5 Axles	A = 2.60 L = 27.00	W = 8.53 L = 88.58
C4-R3 (12/22) 	Camion Remolque	Full Truck	A = 2.50 L = 28.50	W = 8.20 L = 93.50
	Seis Ejes	6 Axles	A = 2.60 L = 27.00	W = 8.53 L = 88.58

Footnotes:

A Ancho Del Vehículo	W Width of Vehicle
L Longitud Del Vehículo	L Length of Vehicle
H Altura Del Vehículo 4.15 M	H Height 13.61 Ft

Tipo De Camino / Road Type					
B4 Y B2 M	FT	C M	FT	D M	FT
A = 2.50 L = 23.50	W = 8.20 L = 77.09	A = 2.50 L = 22.50	W = 8.20 L = 73.81	N/A	
A = 2.60 L = 27.00	W = 8.53 L = 73.81	A = 2.60 L = 21.50	W = 8.53 L = 70.53	N/A	
A = 2.50 L = 23.50	W = 8.20 L = 77.09	A = 2.50 L = 22.50	W = 8.20 L = 73.81	N/A	
A = 2.60 L = 27.00	W = 8.53 L = 73.81	A = 2.60 L = 21.50	W = 8.53 L = 70.53	N/A	
A = 2.50 L = 23.50	W = 8.20 L = 77.09	A = 2.50 L = 22.50	W = 8.20 L = 73.81	N/A	
A = 2.60 L = 27.00	W = 8.53 L = 73.81	A = 2.60 L = 21.50	W = 8.53 L = 70.53	N/A	

RESOLUTION OF THE WESTERN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS
REGARDING

ADOPTING THE SIXTH EDITION OF "A GUIDE FOR UNIFORM LAWS AND REGULATIONS GOVERNING
TRUCK SIZE AND WEIGHT AMONG THE WASHTO STATES"

WHEREAS, Resolution 1-90, approved by the WASHTO Policy Committee, April 6, 1990, adopted the first edition of the "GUIDE"; and

WHEREAS, Resolution 1-90 recognized that the "GUIDE" should be a continuing and dynamic document; and

WHEREAS, Resolution 7-93, 7-95, 3-97, and 4-99 approved by the WASHTO Policy Committee, adopted the second, third, fourth, and fifth editions to the "GUIDE" and, accordingly, is proposing a sixth edition;

NOW, THEREFORE, BE IT RESOLVED that the WASHTO Policy Committee hereby adopts this sixth edition of "A GUIDE FOR UNIFORM LAWS AND REGULATIONS GOVERNING TRUCK SIZE AND WEIGHT AMONG THE WASHTO STATES" (Changes summarized in Attachment A); and

BE IT FURTHER RESOLVED that the WASHTO Policy Committee continues to support the work of the Committee on Highway Transport to resolve highway transportation issues in the WASHTO member states and to propose further updates and amendments to the "GUIDE" as deemed necessary; and

BE IT FURTHER RESOLVED that the WASHTO Policy Committee continues to encourage the individual states to incorporate, to the extent possible, the recommendations of the "GUIDE" into laws, regulations and policies of all the WASHTO states in order to accomplish increased efficiency of interstate truck transportation in the WASHTO region.

Adopted by the WASHTO Policy Committee in June 2004.

